

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-21090-00-00  
Spot: SENW Sec/Twnshp/Rge: 14-29S-18W  
3362 feet from S Section Line, 3290 feet from E Section Line  
Lease Name: UNRUH Well #: 4-B  
County: KIOWA Total Vertical Depth: 5041 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3500		WITH 2 SX CMT
SURF	8.625	532		WITH 400 SX CMT
PROD	4.5	5009	0	WITH 500 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/01/2011 8:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: SHANE PELTON Company: HERMAN L. LOEB Phone: (719) 340-8987

Proposed Plugging Method: SET CIBP@ 4850' WITH 2 SX CMT. PRESSURE TEST CASING. PERFORATE @ 1175' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/01/2011 10:55 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

STACKED OUT AT 3999'. SET CIBP @ 3500' WITH 2 SX CMT. PRESSURE TEST CASING TO 335#. PERFORATE @ 1175' & PUMPED 225 SX CMT AT 800# @ 2 BPM WITH LITTLE OR NO BLOW. SHUT IN WITH 200#. TIED ONTO BACKSIDE & PUMPED 125 SX CMT. SHUT IN WITH 200#.

Perfs:

Top	Bot	Thru	Comments
4906			
4893			

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

RECEIVED  
SEP 13 2011  
KCC WICHITA

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED

SEP - 8 2011

KCC DODGE CITY

Form CP 2/3

9/14/11