

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21764-00-00
Spot: NE Sec/Twnshp/Rge: 11-28S-33W
3986 feet from S Section Line, 1364 feet from E Section Line
Lease Name: GUTTRIDGE Well #: 2
County: HASKELL Total Vertical Depth: 2901 feet

Operator License No.: 33988
Op Name: LEBOSQUET GAS OPERATIONS, LLC
Address: 535 S EMPORIA STE 103
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2650		WITH 2 SX CMT
SURF	8.625	850		WITH 150 SX CMT
PROD	4.5	2898	0	WITH 550 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/06/2011 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 2650' WITH 2 SX CMT. PLUG AT 1700' WITH 25 SX CMT. PERFORATE 5 1/2" @ 880' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: PARTIAL
Date/Time Plugging Completed: 09/06/2011 2:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 2650' WITH 2 SX CMT. PUMPED 25 SX CMT AT 1700'. PERFORATE 5 1/2" @ 875' & UNABLE TO PUMP INTO. PERFORATE 5 1/2" @ 862 & PUMPED 225 SX CMT WITHOUT GETTING CMT TO SURFACE. SDFW. 9/6/11: 5 1/2" CASING STANDING FULL OF CMT. RIH W/1" TBG BETWEEN 8 5/8" & 5 1/2" CASING. TAGGED TOC @ 120'. PUMPED 50 SX CMT FILLING ANNULUS TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2821	2840		
2776	2788		
2762	2768		
2724	2738		
2698	2706		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

RECEIVED
SEP 13 2011
KCC WICHITA

District: 01

Signed Jack MacLaskey
(TECHNICIAN)

RECEIVED
SEP - 7 2011
KCC DODGE CITY

9/14/11