

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21698-00-00
Spot: NESWSESE Sec/Twnshp/Rge: 32-27S-18W
600 feet from S Section Line, 700 feet from E Section Line
Lease Name: NAUMANN Well #: 1-32
County: KIOWA Total Vertical Depth: 493 feet

Operator License No.: 33036
Op Name: STRATA EXPLORATION, INC.
Address: PO BOX 401
FAIRFIELD, IL 62837

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF		481		WITH 375 SX CMT

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 08/26/2011 12:00 PM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: SHANE DOWNS Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 08/26/2011 7:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

Perfs:

LOST CIRCULATION. RAN TEMP. LOG. TOC @ 110'. PUMP 175 SX CMT AT 110' THROUGH 1". NO FILL. PUMPED 100 SX CMT THROUGH 1" NO FILL. NEXT TRIED TO FILL ANNULUS WITH 75 SX HULLS & 5 YDS OF PEA GRAVEL FOLLOWED BY 45 YDS OF QUICK CRETE. COLLAPSE CASING @ 72'. 1ST PLUG BAFFLE PLATE 1 JOINT ABOVE SHOE JOINTS. 20' OF CMT ON TOP OF BAFFLE LEFT OVER FROM FIRST CEMENT JOB. 2ND PLUG RUN IN HOLE WITH DRILL PIPE & SPOT 20 SX CMT. CMT AT 60'. 3RD PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 4TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: DP

RECEIVED
SEP 13 2011
KCC WICHITA

District: 01

Signed

Steve Durrant

(TECHNICIAN)

RECEIVED

SEP 12 2011

KCC DODGE CITY

Form CP-2/3

9/14/11