

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20804-00-01
Spot: SWSWSE Sec/Twnshp/Rge: 23-30S-18W
344 feet from S Section Line, 2299 feet from E Section Line
Lease Name: VIEUX Well #: 2
County: KIOWA Total Vertical Depth: 5216 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	553		WITH 400 SX CMT
PROD	5.5	5186	1823	250 SX

Well Type: EOR UIC Docket No: E24176.4 Date/Time to Plug: 09/02/2011 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PUMP 50 SX CMT THROUGH TBG AT 3920'. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 570' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/02/2011 1:45 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

LEFT STUCK CASING IN HOLE FROM 1120' TO 640' PUMP 50 SX CMT THROUGH TBG TO 3920'. 1ST PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 560' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5080	5143		
4915	4925		MARMATON

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED
SEP 13 2011

KCC WICHITA

District: 01

Signed Kenny M Sullivan
(TECHNICIAN)

RECEIVED
SEP 12 2011

KCC DODGE CITY

Form CP-243
9/14/11