

6-3-88

191 P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171-20,370-0000
SE SW NW, SEC. 36, T 18 S, R 32 WAE

2970 feet from S section line
4290 feet from E section line

Lease Name Treger Well # 36-1

County Scott 153.40

Well Total Depth 4720 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 438

TECHNICIAN'S PLUGGING REPORT

Operator License # 9883

Operator: Sharon Resources, Inc.

Name & Address 7100 East Belleview Ave., Suite 201

Englewood, CO 80111

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Western Kansas Drilling License Number 4083

Address Box 126, Hays, KS 67601

Company to plug at: Hour: 7:15 p.m. Day: 2 Month: 6 Year: 19 88

Plugging proposal received from Frank Taggart

(company name) Western Kansas Drilling (phone) 913-628-2296

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2976'
Anhydrite 2284-2301'

1st plug at 2300' with 50 sx cement, 2nd plug at 1500' with 80 sx cement,

3rd plug at 450' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:30 a.m. Day: 3 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2300' with 50 sx cement,

2nd plug at 1500' with 80 sx cement,

3rd plug at 450' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED (XXXX) did not observe this plugging.

DATE 7-15-88

INV. NO. 21364

Signed Stephan J. Pfeifer
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

JUN - 6 1988
6-6-88

CONSERVATION DIVISION
Wichita, Kansas