

TO: STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-019-20729-00-01  
Spot: SWNWSW Sec/Twnshp/Rge: 12-32S-9E  
1650 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: INMAN Well #: 2  
County: CHAUTAUQUA Total Vertical Depth: 2530 feet

Operator License No.: 5120  
Op Name: RANGE OIL COMPANY, INC.  
Address: 125 N MARKET ST STE 1120  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	107		
PROD	4.5	2211		245 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/06/2011 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ALAN NATION Company: \_\_\_\_\_ Phone: (620) 222-4304

Proposed Plugging Method: Set 35 sack cement plug at 1000'. Then cement from 500' to surface.

Plugging Proposal Received By: STEVE KORF WitnessType: PARTIAL  
Date/Time Plugging Completed 07/07/2011 3:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to 2100' and spotted 35 sack plug with 3% gel and hulls. Pulled up to 1300' and spotted 35 sack plug with 3% gell and hulls. Pulled tubing out of well. On 7-7-11 ran 17 joints of tubing back in well to 550' and circulated cement to surface. Pulled 2" and topped well off. A total of 125 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
2156	2163		
1073	1080		

RECEIVED

SEP 6 2011 DAS

KCC Chanute Dist. #3


RECEIVED  
SEP 14 2011  
KCC WICHITA

Remarks: WELL PLUGGED DUE TO DENIED TA.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)