

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-30234-00-01
Spot: S2SESE Sec/Twnshp/Rge: 25-29S-5E
304 feet from S Section Line, 666 feet from E Section Line
Lease Name: BROWN UNIT Well #: 9
County: BUTLER Total Vertical Depth: 2790 feet

Operator License No.: 9594
Op Name: GREER, TOM
Address: PO BOX 2444
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	232		180 SX
T1	2.875	2560		TUBING STRING CONSISTS OF 2 SIZES TUBING 2 7/8 AND 2 3/8.
PROD	5.5	2790		100 SX

Well Type: EOR UIC Docket No: E27664.1 Date/Time to Plug: 08/15/2011 8:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Rcvd. from: TOM GREER Company: GREER OIL CO. Phone: (580) 761-1750

Proposed Plugging Method: AS PER KCC RULES & REGS / USING 2-3/8" BIT TO CLEAN OUT TO TD. WILL LOAD TBG W/CEMENT & PUSH 2-7/8" WIPER PLUG TO 2500'. WILL 1" BACKSIDE FROM 300'-0', THEN 1" DOWN TBG FROM 300'-0'.

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/17/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

8-16-2011, RIH W/BIT & TBG CIRCULATING HOLE CLEAN @ 2450, CIRCULATED HOLE CLEAN, SDON. 8-17-2011, RIH W/TBG AND LOWERED @ 2560', CONSOLIDATED MIXED & PUMPED 15 SXS CLASS A COMMON 1% CC AND DISPLACED IN TUBING. LAYED DOWN WORKOVER STRING & BIT. WAITED 2 HOURS, TAGGED CEMENT @ 2457'. CUT WINDOW BETWEEN 5-1/2" CSG & 8-5/8" CASING & RIH W/1" TBG @ 132', CONSOLIDATED ESTABLISHED CIRCULATION MIXED & PUMPED 70 SXS CLASS A COMMON 1% CC TO SURFACE, LAYED DOWN 1" TBG AND RIH INSIDE 2-7/8" TBG @ 300', CONSOLIDATED ESTABLISHED CIRCULATION AND MIXED & PUMPED 15 SXS CLASS A COMMON 1% CC TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #31208.

Perfs:

Top	Bot	Thru	Comments
2742	2748	CSG	
2730	2734	CSG	
2712	2722	CSG	

RECEIVED
SEP 14 2011
KCC WICHITA

Remarks: PACKER SET & CEMENTED @ 2560' / COMPLIANCE, FAILED MIT

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

cc to MIC 9/15/11
9/16/11