

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-24540-00-00
Spot: SWNENENW Sec/Twnshp/Rge: 8-34S-11E
4645 feet from S Section Line, 3292 feet from E Section Line
Lease Name: BETTY CASEMENT Well #: 5
County: CHAUTAUQUA Total Vertical Depth: 1273 feet

Operator License No.: 7644
Op Name: MILLER, BOBBY ELZO
Address: 2061 INDEPENDENCE RD UNIT 23
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40		
PROD	4.5	1273		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/02/2011 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: BOB MILLER Company: _____ Phone: (620) 725-3917

Proposed Plugging Method: PUMP 2 SKS GEL THEN 5 SKS CEMENT AT PERFS, PULL UP TO 900' PUMP 5 SKS CEMENT, PULL UP TO 350' AND CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed 06/02/2011 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1220' gelled hole and spotted 5 sack plug. Pulled up to 900' and spotted 5 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 45 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1236	1250		
1228	1234		

RECEIVED

SEP 6 2011 DAS

KCC Chanute Dist. #3


RECEIVED
SEP 14 2011
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

Form CP-2/3
9/16/11