

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-049-22549-00-00
Spot: NWSESENW Sec/Twnshp/Rge: 12-30S-12E
3115 feet from S Section Line, 3240 feet from E Section Line
Lease Name: CODY Well #: 101
County: ELK Total Vertical Depth: 1829 feet

Operator License No.: 7786
Op Name: CODY, KEN L.
Address: 1125 RD 27
LONGTON, KS 67352

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	43		16 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/07/2011 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: KEN L. CODY Company: _____ Phone: (620) 642-6123

Proposed Plugging Method: CEMENTING TO BE DONE THROUGH 2 3/8" TUBING. GEL HOLE @ 1800'. SPOT 12 SX OF CEMENT @ 1800' - PULL UP TO 1550' AND SPOT 12 SX OF CEMENT. PULL UP TO 850' AND SPOT 12 SX OF CEMENT. PULL UP TO 350' AND CEMENT TO SURFACE W/ 104 SX CEMENT.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 07/07/2011 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1800' gelled hole and spotted 12 sack plug. Pulled up to 1550' and spotted 12 sack plug. Pulled up to 850' spotted 12 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 140 sacks of cement were used to plug this well.

RECEIVED
SEP 6 2011
KCC Chanute Dist. #3
DAS


RECEIVED
SEP 14 2011
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)