

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20446-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 28-22S-18E
1008 feet from S Section Line, 5053 feet from E Section Line
Lease Name: SPENCER Well #: 1
County: ANDERSON Total Vertical Depth: 1551 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	65		
PROD	4.5	1547		50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/16/2011 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: RIH W/TBG TO BTM, RUN CMT BOND LOG TO FIND TOP OF CMT PERF JUST ABOVE SAME, TRY TO CIRC, IF SO, RIH W/2 3/8" TBG, SPOT 50' CMT ON BTM, GEL SPACER JUST BELOW PERFS, CIRC CMT ON BACK SIDE OF PROD CSG + INSIDE SAME. IF NO CIRC, SHOOT CSG OFF, POOH, CMT SAME + CMT FROM 300' TO SURFACE.

Plugging Proposal Received By: LEVI SHORT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2011 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 2-INCH PIPE TO 1551 FEET IN 4-1/2 INCH AND PLACE 100 FOOT PLUG. PLACE 100 FOOT PLUG AT 880 FEET THEN SHOOT OFF 4-1/2 INCH AT 854 FEET AND REMOVE. PLACE 50 FOOT PLUG AT 500 FEET AND FROM 300 FEET TO SURFACE. GEL SPACER WAS PLACED BETWEEN CEMENT PLUGS. USE TOTAL OF 127 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
1547	1551		OPEN HOLE

RECEIVED

SEP 6 2011 LS

KCC Chanute Dist. #3

RECEIVED
SEP 14 2011
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

L. Short

(TECHNICIAN)