

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20476-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 28-22S-18E
1636 feet from S Section Line, 5042 feet from E Section Line
Lease Name: SPENCER Well #: 2
County: ANDERSON Total Vertical Depth: 1559 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1340		
SURF	7	40		
PROD	4.5	1553		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2011 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: PERF ABOVE TOP OF CMT, CIRC, IF CAN'T, SHOOT OFF CSG, POOH SAME, RIH W/2 3/8" TBG, PUMP 200' CMT PLUG AT BTM (ABOVE BP), THIS WILL COVER PERFS NOTED ABOVE, GEL SPACER TO JUST BELOW SHOT PT, 100' CMT PLUG, GEL SPACER, CMT FROM 300' TO SURFACE..

Plugging Proposal Received By: LEVI SHORT Witness Type: PARTIAL
Date/Time Plugging Completed: 07/26/2011 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 2-INCH PIPE TO 1340 FEET IN 4-1/2 INCH AND PLACE 100 FOOT PLUG. PLACE 100 FOOT PLUG AT 1030 FEET THEN SHOOT OFF 4-1/2 INCH AT 1008 FEET AND REMOVE. PLACE 50 FOOT PLUG AT 500 FEET AND FROM 300 FEET TO SURFACE. GEL SPACER WAS PLACED BETWEEN CEMENT PLUGS. USE TOTAL OF 127 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
1553	1559		ARBUCKLE OPEN
1178	1181		

RECEIVED

SEP 6 2011 LS

KCC Chanute Dist. #3


RECEIVED
SEP 14 2011
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

Form CP-2/3

9/16/11