

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20188-00-01
Spot: NESESW Sec/Twnshp/Rge: 13-31S-3E
1017 feet from S Section Line, 2817 feet from E Section Line
Lease Name: OLSON-RULE Well #: 2
County: COWLEY Total Vertical Depth: 3684 feet

Operator License No.: 5892
Op Name: BERENTZ DRILLING CO., INC.
Address: PO BOX 782228
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	180		175 SX
PROD	5.5	3332		125 SX

Well Type: SWD UIC Docket No: D18144.0 Date/Time to Plug: 08/18/2011 8:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: DARREL WALTERS Company: BERENTZ DRILLING COMPANT, I Phone: (316) 685-5908

Proposed Plugging Method: AS PER KCC RULES & REGS. FILL HOLE W/SAND 50' ABOVE CASING, DUMP BAIL 5 SKS CEMENT ON TOP, PERFORATE & CEMENT FROM 350'-0.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 08/18/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3052', DUMP BAILED 2 SXS CEMENT ON TOP. PERFORATED SQUEEZE HOLES @ 350-351. RIH W/TBG @ 2900'. MIXED AND PUMPED 1200# GEL FOR SPACER FROM 2900'-400'. PULLED TBG @ 360', BROKE CIRCULATION, HURRICANE SERVICES MIXED & PUMPED 67 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TBG, TOPPED WELL OFF, W/GOOD RETURNS ON BACKSIDE. P&A COMPLETE 8-18-2011, 5:00 PM. HURRICANE CEMENT TICKET #4661.

Perfs:

Top	Bot	Thru	Comments
3332	3684	OH	

RECEIVED
SEP 14 2011
KCC WICHITA

Remarks: PLUG DUE TO COMPLIANCE/ FAILED MIT

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

cc to KCC 9/15/11
JK

Form CP-2/3
9/16/11