

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-041-00068-00-00
Spot: NWSWSWSE Sec/Twnshp/Rge: 5-15S-1E
347 feet from S Section Line, 2384 feet from E Section Line
Lease Name: BOURBINA Well #: 1
County: DICKINSON Total Vertical Depth: 2555 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY, L.L.C.
Address: 1704 LIMESTONE RD
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	100		
PROD	5.5	2541	575	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/08/2011 1:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: LEVI KOEHN Company: _____ Phone: (620) 241-2938

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/08/2011 3:30 AM KCC Agent: SHANE JONES

Actual Plugging Report:

WELLS BOTTOM PLUG WAS PLACED WHEN WELL WAS LAID OUT. THEY USED 50 SX CEMENT ON BOTTOM. SUNFLOFWER TAGGED @ 1500'. THEY SANDED PUMPED DOWN TO 1550' HEAVY MUD. THEY RIPPED CASING @ 575' AND LAID IT OUT. THEY SET A BRIDGE PLUG @ 270'. HOLE IS STANDING DRY DOWN TO BRIDGE PLUG. 9/8 SMÓKY HILL CONCRETE OUT AND DUMPED SLURRY DOWN HOLE TILL RAN OUT OF SLURRY TK #030103. 9/9 I CHECKED THE TOP PLUG AND FOUND IT DOWN 20' PLUS. SUNFLOWER WILL DRY SACK THE WELL TO SURFACE AFTER THE CUT OFF CASING.

Perfs:

Top	Bot	Thru	Comments
2541	2555	OH	


RECEIVED
SEP 14 2011
KCC WICHITA

Remarks: WELL DID NOT HAVE A CURRENT CP-111 ON FILE.

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

Form CP-2/3
9/16/11

SK