

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-22562-00-00  
Spot: NENESE Sec/Twnshp/Rge: 28-20S-21W  
2340 feet from S Section Line, 343 feet from E Section Line  
Lease Name: BIEBER Well #: 1  
County: NESS Total Vertical Depth: 4450 feet

Operator License No.: 7775  
Op Name: WILTON PETROLEUM, INC.  
Address: PO BOX 391  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4360		WITH 2 SX CMT
SURF	8.625	625		WITH 375 SX CMT
PROD	5.5	4448	0	WITH 100 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/24/2011 1:00 PM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: BERNIE RUNDSTROM Company: WILSTON PETROLEUM Phone: (620) 628-4466

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/24/2011 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG SET CIBP @ 4360' & 2 SX CMT. 2ND PLUG LOADED HOLE WITH WATER AND RAN BOND LOG. TOC WAS FOUND @ 740'. RIHWT TO 1500' & PUMPED 30 SX CMT. 3RD PLUG RU WIRELINE TO PERFORATE CASING. 1ST SHOT WENT OFF @ 150' ACCIDENTALY. 2ND SHOT WAS AT 625'. TIHWTAP TO 180'. PUMPED 95 SX CMT. 4TH PLUG TOOHWP & PUMP ADDITONAL 65 SX CMT THAT CIRCULATED TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
4390	4398		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

  
(TECHNICIAN)

RECEIVED  
SEP - 7 2011  
KCC DODGE CITY

RECEIVED  
SEP 15 2011  
KCC WICHITA

Form CP-28  
9/16/11