

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-049-19263-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 9-30S-9E
1650 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HYDE Well #: 14
County: ELK Total Vertical Depth: 2581 feet

Operator License No.: 4448
Op Name: PERKINS OIL ENTERPRISES, INC.
Address: PO BOX 707
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.188	2556		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/31/2011 8:00 AM
Plug Co. License No.: 34203 Plug Co. Name: PIRATE WELL SERVICE, LLC
Proposal Rcvd. from: J. R. PERKINS Company: _____ Phone: (620) 374-2301

Proposed Plugging Method: Perf casing at 1440' & 500' run tubing to bottom & pump gel & spot 5 sacks cement. Pull tubing to 1440' & pump gel & pump 5 sacks of cement. Pull tubing to 500' & pump cement to surface, pull rest of tubing & top off.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed 05/31/2011 3:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Perforated at 1440' and 500'. Ran 2" to 2538' gelled hole and spotted 12 sack plug. Pulled up to 1422' and spotted 12 sack plug. Pulled up to 495' and circulated cement to surface. Pulled 2" and topped well off. A total of 220 sacks of cement were used to plug this well.

RECEIVED

SEP 9 2011 DAS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

Duane Sims

(TECHNICIAN)

RECEIVED

SEP 15 2011

Form CP-2/3

9/16/11

KCC WICHITA