

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20819-00-00
Spot: NWSESWSE Sec/Twnshp/Rge: 19-18S-31W
550 feet from S Section Line, 1675 feet from E Section Line
Lease Name: MCKEAN-PRATT Well #: 15D-19-1831
County: SCOTT Total Vertical Depth: 4800 feet

Operator License No.: 33476
Op Name: FIML NATURAL RESOURCES, LLC
Address: 410 17TH ST STE 900
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	372		WITH 240 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/26/2011 6:15 PM
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC
Proposal Rcvd. from: GARY DOKE Company: FIML NATURAL RESOURCES Phone: (303) 893-5073

Proposed Plugging Method: 1ST PLUG AT 2245' WITH 50 SX CMT. 2ND PLUG AT 1550' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 400' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 08/26/2011 8:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

1ST PLUG AT 2245' WITH 50 SX CMT. 2ND PLUG AT 1550' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 400' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED

SEP - 8 2011

KCC DODGE CITY

Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED

SEP 15 2011

KCC WICHITA

Form 5073
9/16/11