

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25052-00-00
Spot: SWSWNESW Sec/Twnshp/Rge: 8-16S-23W
1532 feet from S Section Line, 1606 feet from W Section Line
Lease Name: BEAMER Well #: 1-8
County: NESS Total Vertical Depth: 4550 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	215		CEMENTED WITH 150 SX CMT
PC		1886		WITH 135 SX CMT
PROD	5.5	4549	0	WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/25/2011 2:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN JOHNSON Company: GRAND MESA OPERATING Phone: (620) 617-3357

Proposed Plugging Method: PUMP 35 SX CMT & 150# HULLS, GEL SPACER TO ANHYDRITE THEN CMT TO SURFACE. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/25/2011 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 35 SX CMT & 200# HULLS, 55 BBL GEL SPACER & 190 SX CMT.
MAXIMUM PRESSURE 3000#. SHUT IN PRESSURE 1800#. TIED ONTO BACKSIDE &
PUMPED 10 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4458	4465		


Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED
SEP - 7 2011
KCC DODGE CITY

Signed


(TECHNICIAN)

RECEIVED
SEP 15 2011
KCC WICHITA