

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24543-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 8-18S-22W  
535 feet from N Section Line, 2286 feet from E Section Line  
Lease Name: MOORE Well #: 1-8  
County: NESS Total Vertical Depth: 4425 feet

Operator License No.: 9855  
Op Name: GRAND MESA OPERATING COMPANY  
Address: 1700 N WATERFRONT PKWY BLDG 600  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	218		WITH 160 SX CMT
PC		1510		WITH 175 SX CMT
PROD	5.5	4422	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/25/2011 11:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JOHN JOHNSON Company: GRAND MESA OPERATING Phone: (620) 617-3357

Proposed Plugging Method: PUMP 35 SX CMT & 150# HULLS, GEL SPACER TO ANHYDRITE & CMT TO SURFACE. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/25/2011 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 35 SX CMT & 200# HULLS, 57 BBL GEL SPACER & 150 SX CMT. MAXIMUM PRESSURE 2200#. SHUT IN PRESSURE 1200#. TIED ONTO BACKSIDE & PUMPED 25 SX CMT. PRESSURED TO 500# & HELD.

Perfs:


Top	Bot	Thru	Comments
4251	4258		
4240	4251		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED

SEP - 7 2011

KCC DODGE CITY

RECEIVED

SEP 15 2011

KCC WICHITA

Form C-2/3

9/16/11