

To: 1 020521  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-071-20,579-06-00 221/2  
C NE NE, SEC. 31, T 16 S, R 42 W/E  
660 feet from N/S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 9855  
Operator: Grand Mesa Operating Company  
Name & Address: 200 E. 1st St., Ste. 307  
Wichita, KS 67202

Lease Name Regier Well # 1-31  
County Greeley 170.63  
Well Total Depth 5250 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 476

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company License Number 30606  
Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 12:30 p.m. Day: 17 Month: 10 Year: 1992

Plugging proposal received from Keith Van Pelt  
(company name) Murfin Drilling Company (phone) 316-267-3241

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2674-2704'  
1st plug at 2700' with 50 sx cement, 2nd plug at 1300' with 50 sx cement,  
3rd plug at 700' with 50 sx cement, 4th plug at 500' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None y

Operations Completed: Hour: 8:10 p.m. Day: 17 Month: 10 Year: 1992

ACTUAL PLUGGING REPORT 1st plug at 2700' with 50 sx cement,  
2nd plug at 1300' with 50 sx cement,  
3rd plug at 700' with 50 sx cement,  
4th plug at 500' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floeal by Allied.  
If additional description is necessary, use BACK of this form.

I (did not) observe this plugging.  
11-4-92  
36682

Signed Glenn R. Barlow (TECHNICIAN)  
RECEIVED STATE CORPORATION COMMISSION 10-22-92 OCT 22 1992  
CONSERVATION DIVISION Wichita, Kansas

EFFECTIVE DATE: 10-6-92  
DISTRICT # 11

State of Kansas  
NOTICE OF INTENTION TO DRILL 071-20,579-0000

FORM MUST BE TYPED  
FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date October 8th 1992  
month day year

NE NE Sec 31 Top 16 S. Rg 42 East West

OPERATOR: License # 9855  
Name: Grand Mesa Operating Company  
Address: 200 E. First St., Suite 307  
City/State/Zip: Wichita, KS 67202  
Contact Person: Ronald N. Sinclair  
Phone: (316) 265-3000

660 feet from SOUTH / North line of Section  
660 feet from East / WEST line of Section  
IS SECTION X REGULAR        IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Greeley  
Lease Name: Regier Well #: 1-31  
Field Name: Wildcat

CONTRACTOR: License #: advise prior to spudding  
Name: Unknown  
Murphy

Is this a Prorated/Spaced Field? yes X no  
Target Formation(s): MARIOW  
Nearest lease or unit boundary: 660 ft  
Ground Surface Elevation: 3864 est feet MSL

Well Drilled For: Well Class: Type Equipment:  
X. Oil ... Enh Rec ... Infield X Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWM ... Disposal X Wildcat ... Cable  
... Seismic; ... # of Holes ... Other  
... Other .....

Water well within one-quarter mile: yes X no  
Public water supply well within one mile: yes X no  
Depth to bottom of fresh water: 220 ft 270  
Depth to bottom of usable water: 1920 ft  
Surface Pipe by Alternate: 1 X 2  
Length of Surface Pipe Planned to be set: 240 290  
Length of Conductor pipe required: 0-

If OWM: old well information as follows:  
Operator: .....,  
Well Name: .....,  
Comp. Date: ....., Old Total Depth .....

Projected Total Depth: 5200  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:  
... well ... farm pond X ... other

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, true vertical depth: .....,  
Bottom Hole Location: .....

DNR Permit #: .....,  
Will Cores Be Taken?: yes X no  
If yes, proposed zone: .....,  
290' Alt. II Req.

Exp. 4/1/93

AFFIDAVIT \* 290 Ft. Surface Pipe Min. Req \*

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101. et. seq.

Pusher Kath Van Pelt  
SPUD DATE 10-9-92 INIT SR  
LENGTH SURFACE PLANNED 300+  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect.        bbls.        when done        bbls.  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 4 1/2 @ 8 5/8 CONDUCTOR  
ANHYDRITE T- 2674 B- 2704 ELEVATION  
TD 5250 FORMATION  
RAN PIPE @        DV TOOL        ALT II DONE  
       SX        Y        N  
       Arbuckle Plug @        Ft. W/        SX  
       Hug./Council @        Ft. W/        SX  
       Anhydrite Base @ 2700 Ft. W/ 30 SX  
       1/2 Base Anyh. @ 1300 Ft. W/ 90 SX  
       1/2, 1/2 Plug @ 700 Ft. W/ 50 SX  
       Bottom Surface @ 500 Ft. W/ 50 SX  
       40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 40 SX  
WATER WELL        SX (Irr. Well        Pond       )  
TECHNICIAN CB DATE 10-16-92 Hauling  
TYPE OF CEMENT 60/40 per 609/21 14 1/2 10.50  
STARTING TIME 8:30 (AM/PM) DATE 10-17-92  
COMPLETION TIME 10:10 (AM/PM) DATE 10-17-92  
STATE COMPLETION COMMISSION  
Wichita, Kansas  
CONSERVATION DIVISION  
WATER RESOURCES DIVISION  
WATER RESOURCES DIVISION