

To: 1 040725
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-071-20,583-00-60 122P
SW NE SE, SEC. 28, T 16 S, R 42 W~~AK~~

TECHNICIAN'S PLUGGING REPORT

Operator License # 3317

Operator: Beard Oil Company
Name: Beard Oil Company
Address: 5600 N. May Ave., Ste. 200
Oklahoma City, OK 73112

1615 feet from S section line
990 feet from E section line

Lease Name Gano Trust Well # 1-28
County Greeley

Well Total Depth 5250 170.63 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 369

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company, Inc. License Number 30606

Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 9 p.m. Day: 19 Month: 12 Year: 19 92

Plugging proposal received from Ed McKenna

(company name) Murfin Drilling Company, Inc. (phone) 316-267-3241

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2678-2706'
1st plug at 2706' with 50 sx cement, 2nd plug at 2000' with 80 sx cement,
3rd plug at 1000' with 50 sx cement, 4th plug at 400' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11 p.m. Day: 19 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2706' with 50 sx cement,
2nd plug at 2000' with 80 sx cement, 3rd plug at 1000' with 50 sx cement,
4th plug at 400' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

1-19-92
I (name) did not observe this plugging.

DATE 1-19-92
37220

Signed Stephen J. Pfeifer
(TECHNICIAN)
RECEIVED
12-22-92
DEC 22 1992
FORM CP-2/3

EFFECTIVE DATE: 11-21-92
DISTRICT # 1
STATE: OKLAHOMA

State of Kansas
NOTICE OF INTENTION TO DRILL 071-20,583-00-00 ALL BLANKS MUST BE FILLED

Must be approved by the K.S.C. five (5) days prior to commencing well

Expected Spud Date: December 1st 1992
month day year

OPERATOR: License # 3317
Name: Beard Oil Company
Address: 5600 North May Ave Suite 200
City/State/Zip: Oklahoma City, Ok 73112
Contact Person: Ivan D. Allred, Jr.
Phone: (405) 842-2333

CONTRACTOR: License # 30606
Name: Murfin Drilling Company, Inc.

Well Drilled For: Well Class: Type Equipment:
Oil Enh Rec Infield Mud Rotary
Gas Storage Pool Ext Air Rotary
GWD Disposal Wildcat Cable
Seismic: # of Holes Other

If OLD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

Exp. 5/16/93

AFFIDAVIT

240' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Ed McKinney
SPUD DATE 12-11-92 INIT. CA
LENGTH SURFACE PLANNED 350
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 369' CONDUCTOR
ANHYDRITE T- 2678 B-2706 ELEVATION
TD 5250 FORMATION Miss
RAN PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ 40565 Ft. W/ SX
Anhydrite Base @ 2706 Ft. W/ 50 SX
1/2 Base Anyh. @ 2000 Ft. W/ 80 SX
1/2, 1/2 Plug @ 1000 Ft. W/ 50 SX
Bottom Surface @ 400 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN S.P. DATE 12-18-92
TYPE OF CEMENT 60/40 puz @ 50 gal 1/4" Flow Seal
STARTING TIME 9:00 (AM/PM) DATE 12-19-92
COMPLETION TIME 11:00 (AM/PM) DATE 12-19-92
CEMENT COMPANY ALICED