

417

To: 1 070835  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-071-20,517-00-00  
NW NW SE, SEC. 28, T 16 S, R 42 W/E  
2310 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 3007

Lease Name Woman Creek Well # 1

Operator: Western Kansas Exploration  
Name & Address: P.O. Box 126  
Hays, KS 67601

County Greeley 168.35

Well Total Depth 5180 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Western Kansas Drilling License Number 4083

Address P.O. Box 126, Hays, KS 67601

Company to plug at: Hour: 2:45 p.m. Day: 19 Month: 7 Year: 19 90

Plugging proposal received from Frank Taggart

(company name) Western Kansas Drilling (phone) 913-628-2296

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2667-2702'  
1st plug at 2700' with 50 sx cement, 2nd plug at 2000' with 50 sx cement,  
3rd plug at 1000' with 50 sx cement, 4th plug at 380' with 40 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:15 p.m. Day: 19 Month: 7 Year: 1990

ACTUAL PLUGGING REPORT 1st plug at 2700' with 50 sx cement,

2nd plug at 2000' with 50 sx cement.

3rd plug at 1000' with 50 sx cement,

4th plug at 380' with 40 sx cement.

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION  
AUG 15 1990  
08-10-90  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal per sx by Halliburton.  
(If additional description is necessary, use BACK of this form.)

INVOICED TO observe this plugging.

Signed Dan Goodrow (TECHNICIAN)

DATE AUG 15 1990

WV. NO. 28937

NOTICE OF INTENTION TO DRILL S-071-20, 517-00-00 ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 06/22/90  
month day year

NW 1W SE Sec 2E Twp 10 S, Rg 12 W West East

OPERATOR: License # 3007  
Name: WESTERN KANSAS EXPLORATION  
Address: P.O. BOX 126  
City/State/Zip: HAYS KS 67601  
Contact Person: STAN YOUNGER  
Phone: (913) 628-2296

2310 feet from South line of Section  
2310 feet from East line of Section  
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License # 40B3  
Name: WESTERN KANSAS DRILLING

County: GREELEY  
Lease Name: WOMAN CREEK Well #: #1  
Field Name: WILDCAT

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Inj ... Infield  Mud Rotary  
 Gas ... Storage  Pool Ext. ... Air Rotary  
 CWMO ... Disposal ... Wildcat ... Cable  
 Seismic; ... # of Holes

Is this a Prorated Field? ... yes  no  
Target Formation(s): MORROW  
Nearest lease or unit boundary: 330  
Ground Surface Elevation: N/A feet MSL  
Domestic well within 330 feet: ... yes  no  
Municipal well within one mile: ... yes  no  
Depth to bottom of fresh water: 200  
Depth to bottom of usable water: 1900  
Surface Pipe by Alternate: ... 1  2  
Length of Surface Pipe Planned to be set: 300  
Length of Conductor pipe required: \*\*\*\*\*  
Projected Total Depth: 5200  
Formation at Total Depth: MORROW  
Water Source for Drilling Operations:  
... well  farm pond ... other

If CWMO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

DWR Permit #: \_\_\_\_\_  
Will Cores Be Taken? ... yes  no  
If yes, proposed zone: \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? ... yes  no  
If yes, total depth location: \_\_\_\_\_

S: Operator - GMT/High Tech Oper #4201 Exp. 12/20/90

AFFIDAVIT

S: Operator - Western Kansas Exploration #3007 250' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, MISSISSIPPI ct. seq.

Pusher Hand SPUD DATE 7-9-90 INIT. rlw  
 LENGTH SURFACE PLANNED 300'  
 RESERVE PIT STATUS- REMOVE FLUID LINED  
 after salt sect. bbbls. when done bbbls.  
 RATHOLED AHEAD? Y N SIZE HOLE CONDUCTOR  
 SURFACE PIPE 8 7/8" @ 371'  
 ANHYDRITE T- 2667 B- 2702 ELEVATION \_\_\_\_\_  
 TD 5180 FORMATION \_\_\_\_\_  
 RAN PIPE @ SX DV TOOL \_\_\_\_\_ ALT II DONE SX Y \_\_\_\_\_ N \_\_\_\_\_  
 Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
 Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
 1 Anhydrite Base @ 2700' Ft. W/ 50 SX  
 2 1/2 Base Anhy. @ 2000' Ft. W/ 50 SX  
 3 1/2, 1/2 Plug @ 1000' Ft. W/ 50 SX  
 4 Bottom Surface @ 380 Ft. W/ 40 SX  
 5 40' Plug @ 40 Ft. W/ 10 SX  
 RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ \_\_\_\_\_ SX  
 WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
 Hauling \_\_\_\_\_  
 TECHNICIAN \_\_\_\_\_ DATE \_\_\_\_\_  
 TYPE OF CEMENT 60/40 67% 1/4<sup>th</sup> fc per sy.  
 STARTING TIME 2:45 (AM/PM) DATE \_\_\_\_\_  
 COMPLETION TIME 5:15 (AM/PM) DATE 7/19-1990  
 CEMENT COMPANY Hall