

1080278

TO: STATE CORPORATION COMMISSION

API NUMBER 15-071-20,712-00-00
APP. NE NW NW SEC. 26, T 16 S, R 42 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1130 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME KRISS WELL # 3-26

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEY

OPERATOR LICENSE # 3581

10/24

WELL TOTAL DEPTH 2718 FEET

88.34

OPERATOR: RED OAK ENERGY INC. PRODUCTION CSG: SIZE " FEET

NAME AND ADDRESS 7701 E KELLOGG, SUITE 710 WICHITA, KS 67207 SURFACE CASING: SIZE 8 5/8" @ 366' WITH SX

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MURFIN DRILLING COMPANY, INC LICENSE NUMBER 30606

ADDRESS 250 N WATER, SUITE 300, WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 12:01 PM DAY: 24 MONTH: 10 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM BERNIE

(COMPANY NAME) MURFIN DRILLING COMPANY, INC (PHONE) 316-267-3241

WERE:

PROPOSED METHOD OF PLUGGING SAME AS ACTUAL METHOD.

 PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 4:25 PM DAY: 25 MONTH: 10 YEAR: 1999

ACTUAL PLUGGING REPORT

SEE ATTACHED PAGE.

INVOICED

DATE 12/7/99

INV. NO. 60938

RECEIVED
STATE CORPORATION COMMISSION
11-02-99
NOV 2 1999

REMARKS: USED ASC WITH 2% CC BY ALLIED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED Karin D. Thurt
(TECHNICIAN) FORM CP-2/3



15-071-20712-00-0

Plugging procedure for Kriss #3-26 Greeley County

On 10/24/99 lost circulation at 1733' and 2587'.

1st plug at 2600' with 50 sx 60/40 pozmix 3-2cc ¼# flo seal.

2nd plug at 1880' with 80 sx cement. Wait on location for 4 hours.

3rd plug at 1880' with 80 sx cement.

4th plug at 1880' with 75 sx ASC cement.

5th plug at 1880' with 75 sx ASC cement.

10/25/99

6th plug Bridge at 2068'. Fill hole with mud. lcm 16-20#'s. Circulate with 75 bbl. Pump 50 sx ASC with 2% cc at 1880'. Wait on location for 1 hour. Filled hole. 1" to fill and circulate.

7th plug at 1200' with 50 sx ASC 2% cc cement.

8th plug at 390' with 50 sx cement.

9th plug at 40-0' with 10 sx cement.

10th plug to circulate rat hole with 15 sx cement.

11th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE REGISTRATION COMMISSION

NOV - 2 1999

STATE REGISTRATION COMMISSION
Topeka, Kansas