

1 120666

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5152

Operator: Lee Banks  
Name & Address: 200 W. Douglas, Suite 550  
Wichita, KS 67202

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company License Number 30606

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 10 p.m. Day: 12 Month: 12 Year: 19 91

Plugging proposal received from Ed McKenna

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2694-2727'  
1st plug at 2730' with 50 sx cement, 2nd plug at 1900' with 50 sx cement,  
3rd plug at 950' with 50 sx cement, 4th plug at 370' with 50 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:30 a.m. Day: 13 Month: 12 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2730' with 50 sx cement;

2nd plug at 1900' with 50 sx cement,

3rd plug at 950' with 50 sx cement,

4th plug at 370' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

(if additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 1-9-92

INV. NO. 34275

Signed Duane Rankin  
(TECHNICIAN)

API NUMBER 15- 071-20,554-00-00 191  
C S/2, SEC. 22, T 16 S, R 42 W/2  
1320 feet from S section line  
2640 feet from W 2 section line  
Lease Name Young Well # 1-22  
County Greeley 169.97  
Well Total Depth 5230 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 341

EFFECTIVE DATE: 12-1-91  
DISTRICT # 1  
SEAT Yes X No

State of Kansas  
NOTICE OF INTENTION TO DRILL 071-20,554-00-00

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date Dec. 1, 1991  
month day year

Spot  
C... S/2- Sec 22.. Twp 16S. S. Rg 42.. X West  
East

OPERATOR: License # 05152  
Name: Lee Banks (d/b/a Banks Oil Co.)  
Address: 200 W. Douglas, Suite 550  
City/State/Zip: Wichita, Kansas 67202  
Contact Person: Lee Banks  
Phone: 316-267-0783

1320 feet from South / West line of Section  
2640 feet from East / West line of Section  
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Greeley  
Lease Name: Young Well #: 1-22  
Field Name: unnamed  
Is this a Prorated/Spaced Field? yes X no

CONTRACTOR: License #: 30606  
Name: Murfin Drilling Co.

Target Formation(s): Morrow, Mississippi  
Nearest lease or unit boundary: 3818 1320  
Ground Surface Elevation: 3818 feet MSL

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Enh Rec ... Infield .X Mud Rotary  
X Gas ... Storage ... Pool Ext. ... Air Rotary  
... OUVU ... Disposal .X Wildcat ... Cable  
... Seismic; ... # of Holes ... Other  
... Other

Water well within one-quarter mile: yes X no  
Public water supply well within one mile: yes X no  
Depth to bottom of fresh water: 190 240  
Depth to bottom of usable water: 190 190  
Surface Pipe by Alternate: 1 .X 2

If OUVU: old well information as follows:  
Operator:  
Well Name:  
Comp. Date: Old Total Depth

Length of Surface Pipe Planned to be set: 340  
Length of Conductor pipe required: -0-  
Projected Total Depth: 5250  
Formation at Total Depth: Mississippi  
Water Source for Drilling Operations:  
... well ... farm pond ... X other

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, true vertical depth:  
Bottom Hole Location:

DNR Permit #:  
Will Cores Be Taken? yes X no  
If yes, proposed zone:

Exp. 5/26/92

AFFIDAVIT

280' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

DEC 30 1991

Pusher Ed Mc Kinna  
SPUD DATE 12-4-91 INIT. MLW  
LENGTH SURFACE PLANNED 340 4858  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLE AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 1/2 @ 341 CONDUCTOR  
ANHYDRITE T- 2674 B- 2727 ELEVATION  
TD 5230 FORMATION  
RAN PIPE @ DV TOOL ALT II DONE  
SX SX Y N  
Arbuckle Plug @ Ft. W/ SX  
Hug./Council @ Ft. W/ SX  
Anhydrite Base @ 2730 Ft. W/ 50 SX  
1/2 Base Anyh. @ 1900 Ft. W/ 50 SX  
1/2, 1/2 Plug @ 950 Ft. W/ 50 SX  
Bottom Surface @ 370 Ft. W/ 50 SX  
40' Plug @ 70 Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX  
WATER WELL SX (Irr. Well Pond Hauling)  
TECHNICIAN DR DATE 12-12-91  
TYPE OF CEMENT 61-40 Bag 670 # 40 weight  
STARTING TIME : (AM/PM) DATE  
COMPLETION TIME 2:30 (AM/PM) DATE 12-12  
CEMENT COMPANY Attila