

To: 1  
STATE CORPORATION COMMISSION 4-23  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 071-20,558-00-00  
C S/2 SE, SEC. 22, T 16 S, R 42 W/E  
660 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31673  
Operator: Convest Energy Corporation  
Name & Address: P.O. Box 309, #6 Spoon Drive  
McCook, NE, 69001

Lease Name Young Well # 2-22  
County Greeley 169.65  
Well Total Depth 5220 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 364

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A   
Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number  
Address

Company to plug at: Hour: 1:30 p.m. Day: 23 Month: 4 Year: 1997

Plugging proposal received from John Mondero  
(company name) Convest Energy Corp. (phone) 308-345-2480

Work: 4 1/2" at 5220' w/550 sx cement, PBTD 5165', Perfs at 5070-78', cement circulated from 1918' to 0 w/400 sx cement  
1st plug pump 25 sx cement with 100 lbs. hulls on bottom,  
2nd plug pump 12 sx gel, and 150 sx cement.

Check backside.

04-30-97

RECEIVED  
PLUGGING SECTION  
MAY 02 1997

Plugging Proposal Received by Mike Maier (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2:45 p.m. Day: 23 Month: 4 Year: 1997

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement and 100 lbs. hulls on bottom,  
2nd plug pumped 12 sx gel and 150 sx cement. Pressure went from 100 psi to 800 psi and held.  
3rd plug pumped 10 sx cement down backside. Pressured to 500 psi and held.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Michael J. Maier (TECHNICIAN)

MAY 02 1997  
48044