

FEB 20 1987

API NUMBER 15-071-20,431-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C W/2 NW NW, SEC. 22, T 16 S, R 42 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4620 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9421

Lease Name Young Cattle Co. Well # 1

Operator: Boger Brothers Drilling, Inc.  
Name & Address P.O. Box 723  
Great Bend, KS 67530

County Greeley 169.65

Well Total Depth 5220 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 324

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Company License Number 8241

Address Box 819, Russell, KS 67665

Company to plug at: Hour: 5:15 p.m. Day: 20 Month: 2 Year: 1987

Plugging proposal received from Hap Halfhill

(company name) Emphasis Oil Company (phone) 913-483-3518

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3827'  
Anhydrite 2695-2726'

1st plug at 2726' with 50 sx cement, 2nd plug at 1300' with 50 sx cement,

3rd plug at 350' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:15 p.m. Day: 20 Month: 2 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 2726' with 50 sx cement,

2nd plug at 1300' with 50 sx cement,

3rd plug at 350' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement,

6th plug to circulate mousehole with 10 sx cement.

STATE CORPORATION COMMISSION

FEB 25 1987

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED  
I did not observe this plugging.

DATE 2-26-87

Signed Glen R. Barlow  
(TECHNICIAN)

INV. NO. 16205

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 2 14 87 month day year

API Number 15-071-20,431-00-00

OPERATOR: License # 9421
Name BOGER BROTHERS DRILLING, INC.
Address P.O. Box 723
City/State/Zip Great Bend, KS 67530
Contact Person Steve Mitchell
Phone 316/792-8151

C-N/2 NW NW Sec. 22 Twp. 16 S, Rg. 42 West
4620 Ft. from South Line of Section
4950 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet
County GREELEY

CONTRACTOR: License #
Name Unknown
City/State Emporium, Mo
Well Drilled For: Oil SWD Infield Mud Rotary
Gas Inj Pool Est Air Rotary
OWWO Expl Wildcat Cable

Lease Name YOUNG CATTLE CO. Well # 1
Ground surface elevation 3820 feet MSL

Domestic well within 530 feet: yes no
Municipal well within one mile: yes no

Depth to bottom of fresh water 280
Depth to bottom of usable water 1700

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

Surface pipe by Alternate: 1 2
Surface pipe planned to be set 300' MIN

Conductor pipe required
Projected Total Depth 5200'
Formation MORROW

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 2-8-87 Signature of Operator or Agent Steve R. Mitchell Title Petroleum Geologist

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 300 feet per Alt.
This Authorization Expires 2-15-87 Approved By

More in 2-12-87 set 8 5/8 to 300' set 1 1/2" / 1 1/2"

C-N/2 NW NW Sec. 22 Twp. 16 S, Rg. 42 West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

- 1st plug @ 0-350' feet depth with continuous
2nd plug @ all water formations feet depth with 50' in length
3rd plug @ top of Mississippi feet depth with 50' in length
4th plug @ top of Arbuckle feet depth with 50' in length
5th plug @
(2) Rathole with
(b) Mousehole with

PUSHER Hop Hoffman
TD 5220 FORMATION
SURFACE PIPE 8 5/8" @ 324'
ANHYDRITE 2695-2726 ELEVATION 3827'
STARTING TIME & DATE
COMPLETION TIME & DATE 9:15 PM 2-20-87
1st PLUG @ 2726 FT. WI 50 SX
2nd PLUG @ 1300 FT. WI 50 SX
3rd PLUG @ 350 FT. WI 40 SX
4th PLUG @ 40 FT. WI 10 SX
RAT HOLE CIRCULATED WI 10 SX
MOUSE HOLE CIRCULATED WI 10 SX
WATER WELL PLUGGED WI SX
CEMENT COMPANY HALLIBURTON
TECHNICIAN P.G.
60/40 per. 67991

STATE CORPORATION COMMISSION
FEB 25 1987
CONSERVATION DIVISION
Wichita, Kansas