

APR 16 1987

9.1-

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,437-00-00

NW NE NW, SEC. 22, T 16 S, R 42 W/E

4950 feet from S section line

3630 feet from E section line

Lease Name Young Cattle Co. Well # 2

County Greeley 169.00

Well Total Depth 5200 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 300

TECHNICIAN'S PLUGGING REPORT

Operator License # 9421

Operator: Boger Brothers Drilling Inc.

Name & Address P.O. Box 723

Great Bend, KS 67530

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations License Number 8241

Address Box 819, Russell, KS 67665

Company to plug at: Hour: 7 p.m. Day: 16 Month: 4 Year: 1987

Plugging proposal received from Hap Halfhill

(company name) Emphasis Oil Operations (phone) 913-483-3518

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3827' Anhydrite 2693-2731'

1st plug at 2735' with 50 sx cement, 2nd plug at 1670' with 80 sx cement,

3rd plug at 330' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:45 p.m. Day: 16 Month: 4 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 2735' with 50 sx cement,

2nd plug at 1670' with 80 sx cement,

3rd plug at 330' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form CONSERVATION DIVISION Wichita, Kansas)

RECEIVED STATE CORPORATION COMMISSION

APR 20 1987

INVOICED

DATE 4-21-87

INV. NO. 16586

Signed Paul A. Luthi (TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date March 19, 1987 month day year

API Number 15-071-20,437-00-00

OPERATOR: License # 9421 Name Roger Brothers Drilling Inc. Address P.O. Box 723 City/State/Zip Great Bend, KS 67530 Contact Person Steve Mitchell Phone 316/792-8151

NW NE NW Sec. 22 Twp. 16 S, Rg. 42 East X West 4950 Ft. from South Line of Section 3630 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet County Greeley

CONTRACTOR: License # 8241 Name Emphasis Drilling Company City/State Russell, Kansas

Lease Name Young Cattle Co Well # 2 Ground surface elevation 3827 feet MSL

Well Drilled For: Oil SWD Gas Inj OWWO Well Class: Infield Pool Ext Wildcat Type Equipment: Mud Rotary Air Rotary Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

If OWWO: old well info as follows:

Depth to bottom of fresh water 240 feet Depth to bottom of usable water 1650 feet

Operator Well Name Comp Date Old Total Depth

Surface pipe by Alternate: 1-2 Surface pipe planned to be set 300 feet

I certify that well will comply with K.S.A. 55-101, et seq. Date 3-16-87 Signature of Operator or Agent Steve R. Mitchell Title Petroleum Geologist

For KCC Use: Conductor Pipe Required 9-17-87 feet; Minimum Surface Pipe Required 260 feet per Alt. This Authorization Expires 3-17-87 Approved By 3-17-87

Set 8 7/8 - 300+ Irrigation well - Spud 4-8-87 5:00 - PM

NW NE NW Sec. 22 Twp. 16 S, Rg. 42 East W West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ Base Anhydrite 50 feet depth with 50 sxs of 2nd plug @ 1700 80 feet depth with 80 sxs of 3rd plug @ 30' under surface 40 feet depth with 40 sxs of 4th plug @ 40-0' 10 feet depth with 10 sxs of 5th plug @ 15 feet depth with 15 sxs of (2) Rathole with 15 sxs (b) Mousehole with 10 sxs

PUSHER Hap Hemphill TD 5200 FORMATION Musr SURFACE PIPE 8 5/8 @ 300' ANHYDRITE 2693 ELEVATION 2738 STARTING TIME & DATE 2:00 PM 4-16-87 COMPLETION TIME & DATE 10:45 PM 4-16-87 1st PLUG @ 2735 FT. W/ 30 SX 2nd PLUG @ 1670 FT. W/ 80 SX 3rd PLUG @ 330 FT. W/ 60 SX 4th PLUG @ 40-0 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ MD CEMENT COMPANY Allied 6/40/87 TECHNICIAN G.A.F.

RECEIVED STATE CORPORATION COMMISSION APR 20 1987 CONSERVATION DIVISION Wichita, Kansas