

To: 1
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202
11-23

API NUMBER 15- 071-20,678-00-00
NE NW NW, SEC. 21, T 16 S, R 42 W2X
330 feet from N2X section line
990 feet from W2X section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 3581
Operator: Red Oak Energy, Inc.
Name & Address: 200 W. Douglas, Ste. 510
Wichita, KS 67202

Lease Name Beck Well / 1-21
County Greeley 190.76
Well Total Depth 5254 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 364

Abandoned Oil Well Gas Well Input Well SWO Well O&A X
Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 30606
Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 6:30 a.m. Day: 23 Month: 11 Year: 19 97

Plugging proposal received from Jim Renner
(company name) Murfin Drilling Co. (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Base Anhydrite 2530'
1st plug at 2530' with 50 sx cement, 2nd plug at 1840' with 80 sx cement,
3rd plug at 900' with 40 sx cement, 4th plug at 400' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 10 a.m. Day: 23 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 2530' with 50 sx cement,
2nd plug at 1840' with 80 sx cement, 11.26.97
3rd plug at 900' with 40 sx cement,
4th plug at 400' with 50 sx cement, 5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

DATE DEC 03 1997
Signed (TECHNICIAN)

KRM REC USE:

EFFECTIVE DATE: 9-16-97

State of Kansas

NOTICE OF INTENTION TO DRILL 071-20,678-00-00 ALL BLANKS MUST BE FILLED

DISTRICT #

Must be approved by the K.C.C. five (5) days prior to commencing well

SEAL Yes X No

Expected Spud Date September 10 1997
month day year

Spot NE NW SW sec 21 Twp 16 S Rg 42 East West

OPERATOR: License # 03581
Name: Red Oak Energy, Inc.
Address: 200 W Douglas #510
City/State/Zip: Wichita, KS 67202
Contact Person: Kevin C. Davis
Phone: (316) 265-9925

330 feet from South (North) line of Section
990 feet from East (West) line of Section
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Greeley

Lease Name: Beck Well #: 1-21
Field Name: Wildcat

Is this a Prorated/Spaced Field? yes X no

Target Formation(s): Morrow

Nearest lease or unit boundary: 330'

Ground Surface Elevation: 3843 feet MSL

Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 280'

Depth to bottom of usable water: 1840'

Surface Pipe by Alternate: 1 X 2

Length of Surface Pipe Planned to be set: 320'

Length of Conductor pipe required: 5250'

Projected Total Depth: 5250'

Formation at Total Depth: Mississippian

Water Source for Drilling Operations: well farm pond X other

DWR Permit #: 300' Alt. II Req.

Will Cores Be Taken? yes no

If yes, proposed zone:

CONTRACTOR: License #: 30606
Name: Murfin Drilling Company

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield ... Mud Rotary
Gas ... Storage ... Pool Ext. ... Air Rotary
O/W/O ... Disposal X Wildcat ... Cable
Seismic: # of Holes ... Other

If O/W/O: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no

If yes, true vertical depth:

Bottom Hole Location:

Exp. 3/11/98

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101 et seq.

Pusher Jim Remora
SPUD DATE 11-13-97 INIT. SR
LENGTH SURFACE PLANNED 320'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 5/8" @ 361' CONDUCTOR
ANHYDRITE T- B-2530 ELEVATION
TD 5254 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 2530 Ft. W/ 50 SX
1/2 Base Anyh. @ 1840 Ft. W/ 80 SX
1/2, 1/2 Plug @ 900 Ft. W/ 40 SX
Bottom Surface @ 400 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 60 SX
RAT HOLE CIRC/W L SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN Sm DATE 11-23-97
TYPE OF CEMENT 64/40 67 1/4 F6 sand
STARTING TIME 6:30 (AM/PM) DATE 11-23-97
COMPLETION TIME 10:00 (AM/PM) DATE 11-23-97
CEMENT COMPANY Allied Cementing