

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,411 -00-00
NE SW , SEC. 17, T 16 S, R 42 W/EX
1980 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9228
Operator: Marlin Oil Corporation
Name & Address 2700 First National Center
Oklahoma City, OK 73102

Lease Name Hobart Well # 1
County Greeley 172.90
Well Total Depth 5320 Mississippi feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 518

Abandoned Oil Well Gas Well Input Well SWD Well D&A X
Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422
Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 1:00 pm Day: 11 Month: January Year: 19 86

Plugging proposal received from Wally Towns
(company name) Abercrombie (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2711-42'
1st plug at 2760' with 60 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug to cover the Dakota with 50 sx cement

4th plug 30' below the base of the surface pipe with 50 sx cement
solid bridge - hulls - plug at 40' -- cement to surface with

5th plug 10 sx cement Plugging Proposal Received by Paul A. Luthi

7th plug to circulate rat hole with 15 sx cement, 8th plug to circulate mouse hole with
10 sx cement (TECHNICIAN)
Plugging operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:00 pm Day: 11 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2760' with 60 sx cement, 2nd plug at 1740' with 80 sx
cement, 3rd plug at 1000' with 50 sx cement, 4th plug at 550' with 50 sx cement,

5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx
cement, 7th plug to circulate rat hole with 15 sx cement, 8th plug to circulate mouse hole
with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 1986

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-16-86

INV. NO. 12211

Signed Paul A. Luthi
(TECHNICIAN)

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

2

Starting Date: 12 26 85
month day year

API Number IS- 071-20,411-00-00

OPERATOR: License # 9228
Name Marlin Oil Corporation
Address 2700 First National Center
City/State/Zip Oklahoma City, OK 73102
Contact Person Dick Lynn
Phone 405-232-3267

NE SW/4 (location) Sec 17 Twp 16 S. Rge 42 East West
1980 Ft North from Southeast Corner of Section
3300 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5422
Name Abercrombie Drilling, Inc.
City/State Wichita, Kansas

Nearest lease or unit boundary line 660 feet.
County Greeley
Lease Name Hobart Well# 1
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
X Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl X Wildcat Cable

Depth to Bottom of fresh water 260 feet
Lowest usable water formation Dakota
Depth to Bottom of usable water 1725 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 500 feet
Conductor pipe if any required None feet
Ground surface elevation 3856 feet MS
This Authorization Expires 6-9-86
Approved By 12-9-85

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 5300 feet
Projected Formation at TD Marrow Sd.
Expected Producing Formations Marrow Sd.

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 12-5-85 Signature of Operator or Agent [Signature] Title Agent [Signature] RCH/KOH

Form C-1 4/84

SPUD - 12-31-85 - 5-6 PM - set SP around midnite

[Handwritten signature]

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 1986
CONSERVATION DIVISION