

To: 1  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 19-071-20,543-00-00

68

C SE SW NE, SEC. 16, T 16 S, R 42 W/E

2970 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5152

Lease Name Floyd Well # 1

Operator: Lee Banks (d/b/a Banks Oil Co.)  
Name & Address 200 W. Douglas, Suite 550  
Wichita, KS 67202

County Greeley 170.30

Well Total Depth 5240 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 8 a.m. Day: 9 Month: 7 Year: 19 91

Plugging proposal received from Ed McKenna

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3821'  
Anhydrite 2726-45'

1st plug at 2745' with 50 sx cement, 2nd plug at 1950' with 80 sx cement,

3rd plug at 1050' with 50 sx cement, 4th plug at 390' with 40 sx cement,

5th plug at 40-0' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 4:30 p.m. Day: 9 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2745' with 50 sx cement,

2nd plug at 1950' with 80 sx cement,

3rd plug at 1050' with 50 sx cement,

4th plug at 390' with 40 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10  
sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by B.J. Services.

(if additional description is necessary, use BACK of this form.)

**INVOICED**

(1991) did not observe this plugging.

DATE 7-22-91

Signed Steve Durrant  
(TECHNICIAN)

INV. NO. 32344

7-9

RECEIVED  
STATE CORPORATION COMMISSION

JUL 12 1991

CONSERVATION DIVISION  
Wichita, Kansas

EFFECTIVE DATE: 7-3-91

FORM MUST BE TYPED  
FORM C-1 4/90

State of Kansas 071-20,543-00-00

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL  
Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date July 2, 1991  
month day year

C SE SW NE Sec 16 Twp 16 S, Rg 42 East West

OPERATOR: License # 05152  
Name: Lee Banks (d/b/a Banks Oil Company)  
Address: 200 W. Douglas, Suite 550  
City/State/Zip: Wichita, Kansas 67202  
Contact Person: Lee Banks  
Phone: 316-267-0783

2970 feet from South line of Section  
1650 feet from East line of Section  
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 6033  
Name: Murfin Drilling Company

County: Greeley  
Lease Name: Floyd Well #: 1  
Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:  
X Oil Inj Infield X Mud Rotary  
X Gas Storage Pool Ext. Air Rotary  
... OAWD Disposal X Wildcat Cable  
... Seismic: # of Holes

Is this a Prorated Field? yes X no  
Target Formation(s): Morrow-Mississippi  
Nearest lease or unit boundary: 330  
Ground Surface Elevation: 3835 feet MSL  
Domestic well within 330 feet: yes X no  
Municipal well within one mile: yes X no  
Depth to bottom of fresh water: 200  
Depth to bottom of usable water: 1950  
Surface Pipe by Alternate: 1 X 2  
Length of Surface Pipe Planned to be set: 340  
Length of Conductor pipe required: -0-

If OAWD: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

RECEIVED  
STATE COMMISSION

Projected Total Depth: 5250  
Formation at Total Depth: Mississippi  
Water Source for Drilling Operations:  
... well ... farm pond X other

Directional, Deviated or Horizontal wellbore? Yes  
If yes, total depth location: Wichita, Kansas

DWR Permit #: \_\_\_\_\_  
Will Cores Be Taken?: yes X no  
If yes, proposed zone: \_\_\_\_\_

Exp. 12/28/91

AFFIDAVIT

310' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Ed McKenna 543  
SPUD DATE 7-1-91 INIT. SM  
LENGTH SURFACE PLANNED 350

RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 1/8 @ 360 CONDUCTOR  
ANHYDRITE T-2726 B-2745 ELEVATION 3821

TD 5250 FORMATION Miss  
RAN PIPE @ DV TOOL ALT II DONE  
SX Y N

Arbuckle Plug @ Ft. W/ SX  
Hug./Council @ Ft. W/ SX  
1 Anhydrite Base @ 2745 Ft. W/ 50 SX  
2 1/2 Base Anhy. @ 1950 Ft. W/ 80 SX  
3 1/2, 1/2 Plug @ 850 Ft. W/ 50 SX  
4 Bottom Surface @ 270 Ft. W/ 40 SX  
5 40' Plug @ 40-0 Ft. W/ 10 SX

RAT HOLE CIRC/W/ 5 SX MOUSE HOLE W/ 12 SX

WATER WELL SX (Irr. Well Pond Hauling X)

TECHNICIAN 50 DATE 7/1/91

TYPE OF CEMENT 60/40 6% 4 # Flow Seal.

STARTING TIME 8:00 (AM/PM) DATE 7-9-91

COMPLETION TIME 4:30 (AM/PM) DATE 7-9-91

CEMENT COMPANY B.J.