

To: 1 051353  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,519 -00-00

SE NE SE, SEC. 15, T 16 S, R 42 W/8  
1800 feet from S section line  
450 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3317

Lease Name Young Well # 4-15

Operator: Beard Oil Company  
Name & Address 5600 North May Ave., Suite 200  
Oklahoma City, OK 73112

County Greeley 169.32  
Well Total Depth 5210 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 357

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 N. Water, #300, Wichita, KS 67202

Company to plug at: Hour: 5:30 a.m. Day: 3 Month: 10 Year: 19 90

Plugging proposal received from Rodney Farr

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2686-2713'

1st plug at 2700' with 50 sx cement, 2nd plug at 1800' with 80 sx cement,

3rd plug at 900' with 50 sx cement, 4th plug at 390' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:30 a.m. Day: 3 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2700' with 50 sx cement,

2nd plug at 1800' with 80 sx cement,

3rd plug at 900' with 50 sx cement,

4th plug at 390' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

WICED  
I (owner/di) observe this plugging.

Signed Richard W. Lacey  
(TECHNICIAN)

10-19-90  
29655  
10-3

EFFECTIVE DATE: 8-20-90

071-20,519-00-00

FORM MUST BE TYPED  
FORM C-1 4/90

State of Kansas

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date August 17 1990  
month day year

SE NE SE Sec 15 Twp 16 S, Rg 42 East X West

OPERATOR: License # 3317  
Name: Beard Oil Company  
Address: 5600 North May Ave., Suite 200  
City/State/Zip: Oklahoma City, OK 73112  
Contact Person: Ivan D. Allred, Jr.  
Phone: (405) 842-2333

1800 feet from South line of Section  
450 feet from East line of Section  
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 6033  
Name: Murfin Drilling Company

County: Greeley  
Lease Name: Young Well #: 4-15  
Field Name: Sidney  
Is this a Prorated Field? X yes X no  
Target Formation(s): Morrow Sands  
Nearest lease or unit boundary: 450'  
Ground Surface Elevation: 3800' (Est.) feet MSL  
Domestic well within 330 feet: X yes X no  
Municipal well within one mile: X yes X no  
Depth to bottom of fresh water: 280'  
Depth to bottom of usable water: 1800'  
Surface Pipe by Alternate: 1 X 2  
Length of Surface Pipe Planned to be set: 350'  
Length of Conductor pipe required: NA  
Projected Total Depth: 5300'  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:  
X well X farm pond X other

Well Drilled For: Well Class: Type Equipment:  
X Oil Inj Infield X Mud Rotary  
Gas Storage Pool Ext. Air Rotary  
OWWD Disposal Wildcat Cable  
Seismic; # of Holes

If OWWD: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? X yes X no  
if yes, total depth location: \_\_\_\_\_

Exp. 2/15/90

300' Alt. II Req.

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Rodney Farr  
SPUD DATE 8-24-90 INIT. R.L.  
LENGTH SURFACE PLANNED 357  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE \_\_\_\_\_  
SURFACE PIPE 2 3/8 @ 357 CONDUCTOR \_\_\_\_\_  
ANHYDRITE T- 2686 B- 2713 ELEVATION \_\_\_\_\_  
TD 3210 FORMATION Miss  
RAN PIPE @ SX DV TOOL 1950 ALT II DONE SX Y N  
Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Anhydrite Base @ 2700 Ft. W/ 50 SX  
1/2 Base Anyh. @ 1800 Ft. W/ 80 SX  
1/2, 1/2 Plug @ 900 Ft. W/ 50 SX  
Bottom Surface @ 390 Ft. W/ 50 SX  
40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX  
WATER WELF 5 SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
TECHNICIAN R.L. DATE 10-1-90 Hauling \_\_\_\_\_  
TYPE OF CEMENTS 90  
STARTING TIME 5:30 (AM/PM) DATE 10-3-90  
COMPLETION TIME 10:30 (AM/PM) DATE 10-3-90  
CEMENT COMPANY Allred