

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20540-00-00
Spot: NESENE Sec/Twnshp/Rge: 15-16S-42W
1650 feet from N Section Line, 330 feet from E Section Line
Lease/Unit Name: YOUNG Well Number: 5-15
County: GREELEY Total Vertical Depth: 5200 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Production Casing Size: 5.5 feet: 5200 WITH 200 SX CMT
Surface Casing Size: 8.625 feet: 357 WITH 235 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/15/2003 1:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: WAYNE Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. MUD TO 2000'. CMT TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/15/2003 3:30 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:


PBTD 5148'. PERFS AT 4970-79'. DV TOOL @ 2097' WITH 300 SX CMT. PUMPED DOWN 5 1/2" CASING 300# HULLS & 25 SX CMT WITH 21 SX GEL SPACER & 175 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN AT 0#. CMT AT SURFACE. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 25 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN AT 500#.

RECEIVED
JUL 24 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed _____

Kevin D. Strube
(TECHNICIAN)

INVOICED

Form CP-2/3