

310

To: 1 070844  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 19-071-20,303-00-00  
C SE NW, SEC. 32, T 17 S, R 39 WXB  
3300 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7271  
Operator: Bartling Oil Company  
Name:  
Address 8550 Katy Freeway, Suite 128  
Houston, TX 77024

Lease Name Johnson Well # 1  
County Greeley 98.31  
Well Total Depth 3025 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Bartling Oil Company License Number 7271

Address 8550 Katy Freeway, Suite 128, Houston, TX 77024

Company to plug at: Hour: 11:10 a.m. Day: 30 Month: 8 Year: 19 90

Plugging proposal received from Terry Maxwell

(company name) Bartling Oil Company (phone) 316-624-1986

were: 4 1/2" at 3005' w/550 sx cement, PBSD 3002', Perfs at 2936-42'

1st plug pump 200 lbs. hulls and 200 sx cement,

2nd plug pump 100 sx cement down backside.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:50 a.m. Day: 30 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 180 sx cement down 4 1/2".

Maximum pressure 700 psi and shut in 100 psi.

Backside would not take at 800 psi.

RECEIVED  
CONSERVATION COMMISSION  
SEP 6 1990

Remarks: Used 60/40 Pozmix 8% gel by Allied. No casing recovery. Wichita, Kansas  
(If additional description is necessary, use BACK of this form.)

INVOICED  
observe this plugging.

Signed Dan Johnson  
(TECHNICIAN)

DATE 9-14-90  
INV. NO. 29300