

1080247

TO: STATE CORPORATION COMMISSION

6-2

API NUMBER 15-071-20,236-00-00
SW SW SW SEC. 30, T 17 S, R 39 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME PLOWMAN WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEY

OPERATOR LICENSE # 6085

WELL TOTAL DEPTH 3050 99.13 FEET

OPERATOR: SMITH CATTLE OIL & GAS PRODUCTION CSG: SIZE 4 1/2" @ 3050' WITH NA SX

NAME AND HC 2 BOX 201 SURFACE CASING: SIZE 8 5/8" @ 278' WITH NA SX

ADDRESS SHARON SPRINGS, KS 67758

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 628, GREAT BEND, KS 67530-0628

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 02 MONTH: 06 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DAVE OLSON

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: PERFS AT 2958-68

1ST PLUG ALLIED PUMPED DOWN 4 1/2" CASING 300# HULLS & 25 SX CEMENT. LET SET 30 MINUTES.

PRESSURED UP TO 1000#. USED 60/40 POZMIX 6% GEL WITH 3% CC.

2ND PLUG PEAK WIRE LINE SERVICE PERFORATED AT 1500'. ALLIED PUMPED DOWN 4 1/2" CASING 80 SX

CEMENT, 100# HULLS, 90 SX CEMENT. SHUT IN AT 300#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 50 SX

CEMENT. SHUT IN AT 100#. PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:00 PM DAY: 02 MONTH: 06 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG ALLIED PUMPED DOWN 4 1/2" CASING 300# HULLS AND 25 SX CEMENT. LET SET 30 MINUTES.

PRESSURED UP TO 1000#. USED 60/40 POZMIX 6% GEL WITH 3% CC.

2ND PLUG PEAK WIRE LINE SERVICE PERFORATED AT 1500'. ALLIED PUMPED DOWN 4 1/2" CASING 80 SX

CEMENT, 100# HULLS, AND 90 SX CEMENT. SHUT IN WITH 300#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS

50 SX CEMENT. SHUT IN WITH 100#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

INVOICED

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

DATE I (DID) OBSERVE THIS PLUGGING. JUN 11 1999

SIGNED Kevin P. Strube (TECHNICIAN) FORM CP-2/3

CONSERVATION DIVISION Wichita, Kansas

INV. NO. 61022