

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-071-20,298-00-00

C.N.W. SW/4 Sec. 5, T 17 S, R 39 W1X

2310 feet from X/S section line

330 feet from W1X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7271

Lease Name NAZARENE Well # 1

Operator: BARTLING OIL COMPANY
Name & Address 8550 KATY FRWY. #128
HOUSTON, TX 77024

County GREELEY

Well Total Depth 3000 feet 97.50

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 7/8 feet 29748' KB

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor KANDRILCO, INC License Number 5889

Address Bldg. 1, Suite 207, 555 N. WOODLAWN, WICHITA, KS 67208

Company to plug at: Hour: 11 AM Day: 16 Month: SEPT. Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO: TERRY MAXWELL w/ HIGGENBOTHAM

(company name) ENGINEERING for KANDRILCO (phone) _____

were: to use 60/40 Pozmix, 2% GEL-3% CC AND SET

1ST plug @ 2595 w/50 sy; 2ND plug @ 1600 w/50 sy;

3RD plug @ 360 w/40 sy; 4TH plug @ 40' w/solid

BRIDGE OF HULLS & RUBBER PLUG AND 10 sy to surface.

Circulate 15 sy w/ THE RATHOLE.

Ordered by J. H. METZ

Signed R. Bartlett
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4 pm Day: 16 Month: SEPT Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered
Cementing by Halliburton

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1983
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

Signed R. Bartlett
(TECHNICIAN)

INVOICE
DATE 9-27-83
INV. NO 5511-W