

15-071-20045-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Derehester Exploration, Inc.
Complete Address 1204 Vaughn Bldg., Midland, Texas 79701
Lease Name Helm Well No. 1
Location GSW Sec. 35 Twp. 18 Rge. (E) (W) 40
County Greely Total Depth 2950'
Abandoned Oil Well Gas Well XX Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Sargent Casing Pulling
Address 620 S. Lincoln, Liberal, Kas License No. 511
Operation Completed: Hour 3 P Day 13 Month 8 Year 1974

The above well was plugged as follows:

- Total Depth 2950' 8 5/8 esg set at 168' ewe 150 sk.
- 5 1/2 esg set at 2944' ew 150 sk.
- 5 1/2 esg PBTB 2890' with perf. (2800-2806)
- Pumped down 5 1/2 esg with 15 sk cement W/100 lbs hulls. Top of cement 2700'.
- Cutoff and recovered 2300' of 5 1/2 esg.
- Pulled 5 1/2 esg to 218' -aire gel -displaced 35 sk cement (218-118)
- Pulled 5 1/2 esg -heavy mud to 33' -set reek bridge & filled to surface with 10 sk cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Masser
Well Plugging Supervisor

DATE 8/20/74
INV. NO. 9738-W