

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Yucca Petroleum Company.

Complete Address P. O. Box #2585, Amarillo, Texas.

Lease Name DeWeese Well No. 1

Location CNW-SE Sec. 6 Twp. 16 Rge. (E) (W) 32

County Scott Total Depth 4880'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated.

Address Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 8:30 PM Day 20 Month 11 Year 1969

The above well was plugged as follows:

395'--8 5/8" Surface casing, cement circulated with 270 Sx.
Top of Dakota section @ 1194'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 100 Sx. cement thru
DP from 1500' to 1050'. Pulled DP to 450' and displaced 25 Sx. cement thru DP from
355'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INDEXED
NOV 24 1969
INV. NO. 893-11