



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

6-13-75

Operator's Full Name Abercrombie Drlg. Inc. & Beren Corp.  
Complete Address 801 Union Center, Wichita Ks.  
Lease Name Graves Well No. #1  
Location NE-SW Sec. 36 Twp. 16 Rge. 31 (E)  (W)   
County SCOTT Total Depth 4670  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Abercrombie Drlg. Inc.  
Address 801 Union Center, Wichita Ks. License No. \_\_\_\_\_  
Operation Completed: Hour 12:00 AM Day 12 Month June Year 1975

The above well was plugged as follows:  
KB. 2912 Dak Top. 2000' SP. 212' of 8 5/8" CWC. 165 sx.  
Pumped down drill stem.  
50 sx cem 50/50 Pozmix 6% Gel @ 900'  
35. " " " " " " @ 840  
Build Bridge To 40'  
10 sx cem 50/50 Pozmix 6% Gel 40' To 0'

I hereby certify that the above well was plugged as herein stated.

Signed: Gilbert D. Hathaway  
Well Plugging Supervisor

INVOICED  
DATE 6/13/75  
INV. NO. 1484-W