

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

*Rec'd
8-12-63*

Operator's Full Name Kewanee Oil Company,

Complete Address: Box # 360, Hoisington, Kansas.

Lease Name Wasinger Well No. A-1

Location NW-NW Sec. 12 Twp. 20 Rge. (E) (W) 33

County Scott Total Depth 4733

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.,

Address: Box # 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 8:00PM Day 9 Month 8 Year 1963

The Above well was plugged as follows:

372'--8 5/8" Surface pipe, cement circulated with 270 Sx.

4682'--5 1/2" cemented with 100 Sx. Well Plugged back to 4657'. Top of perforations @ 4608'

Sanded well back to 4595' and set 5 Sx cement with dump bailer. Pulled 5 1/2" casing to 600', circulated heavy gel mud, (25 Sx.) and displaced 20 Sx. cement. Pulled 5 1/2" to 360' and displaced 20 Sx. cement. Pulled 5 1/2" to 30' and circulated 10 Sx cement to bottom of cellar, Recovered 2009' 5 1/2".

(Cementing & Mudding operations performed by Halliburton)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *H. L. Dicks*
Well Plugging Supervisor

DATE 8/12/63
INV. NO. 7568-W