

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 64-29

LOCATION CW 1/2 - SE 1/4 - SW 1/4

SEC. 11 TWP. 20 RGE. 33-02

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 1 Lease Wasinger "A"

Operator Shallow Water Refining Co. Address 114 W. Pine - Garden City - Kans.

Field _____ County Scott

Total Depth 4668 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4" - 170 ft. Circulated with cement.
5 1/2" casing set at 4641 ft. 300 sacks of cement - Plugged
back with rock & sand to 4575 ft. - Drummed 5 sacks of cement
at 4575 ft. - Shot off & pulled the 5 1/2" casing - mud to 270 ft.
Set rock bridge & 10 sacks of cement at 270 ft.
mud to 35 ft. Plug & 10 sacks of cement
at the surface.
Garnes & Son - Plugging Contractors

STATE CORPORATION COMMISSION
WICHITA, KANSAS

JAN 29 1953
CONSERVATION DIVISION
WICHITA, KANSAS

C. D. Stough
District Conservation Agent

Date 1-18-53

PLUGGING
FILE SEC 11 TWP 20 R 33W
BOOK PAGE 64 LINE 29