

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 54-7

LOCATION CS 1/2-SW-SF

SEC. 10 TWP. 10 RGE. 33W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Roach

Operator The Shallow Water Refining Co. Address Garden City - Kansas

Field _____ County Scott

Total Depth 4680 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 1/4 - 243 ft. Circulated with cement.
5/8 casing set at 4619 ft. Cemented with 15 sacks of
cement. Plugged back to 3950 ft with Mud
Lane Wells Plug & rock - Mixed 5 sacks of cement
at 3950 ft - Shut off & pulled the 5/8 casing - mud
to 255 ft - Set Block Bridge & 20 sacks of cement
at 255 ft - Mud to 30 ft - Plug & 10 sacks at the surface.
By the Pipe Pulling Co - Plugging Contractors

4-23-51

C. A. Stough
District Conservation Agent

Date 4-18-51

PLUGGING
FILE SEC _____ T _____ R _____
BOOK PAGE _____ LINE _____