

15.171.00049.0001

Form CP-3
Rev. 6-4-68

KANSAS

10

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 5 5-69
1968
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company,

Complete Address 1107 North Kansas Avenue, Liberal, Kansas.

Lease Name Rothfelder Well No. 1

Location CSW-SW Sec. 7 Twp. 20 Rge. (E) (W) 33

County Scott Total Depth 4870'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated This well was being used as a SW disposal down the annulus between the 5 1/2" casing and 2" Tubing.

Plugging Contractor Sargent's Casing Pulling Service.

Address Box #506, Liberal, Kansas License No. 511

Operation Completed: Hour 2:30 PM Day 31 Month 10 Year 1969

The above well was plugged as follows:

376'--8 5/8" Surface casing, cement circulated with 200 Sx.
4870'--5 1/2" casing cemented on bottom with 225 Sx. Production packer set @ 4056'.
Tubing parted @ 3114'. Perforations above production packer from 4044' to 4054'.

Squeezed well with 25 Sx. cement, left top of cement @ 3950' and left to set over-
night. Pulled 5 1/2" casing and squeezed well with initially 5 sacks hulls and 8 sacks
gel then 125 Sx. cement from 1000' to 600' and followed with 5 sacks gel from 600' to
400' then 25 Sx. cement from 400' to 320' and followed with 7 sacks gel from 320' to
40' and finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in pressure-
300#. Final shut-in pressure--200#. (Mudding and cementing by Sargents pump truck).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickel
Well Plugging Supervisor

11/5/69
777-4