

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-171-20,223-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name TXO Production Corp.

Complete Address 200 W Douglas Suite 300, Wichita, Kansas 67202

Lease Name Coy Well No. E1

Location 1980FWL-1980FWL Sec. 7 Twp. 20 Rge. 33 (East)(West)

County Scott Total Depth 4865'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Clark Corporation

Address 107 W. Fowler Medicine Lodge, Kansas License No. 583
⁶⁷¹⁰⁴

Operation Completed: Hour: 1:00 PM. Day: 15 Month: July Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They ran 4864' of 4 1/2" production pipe. They plugged the 4 1/2" back to 4742' perforated from 4720' to 24'. 1st plug sandbed the bottom back to 4700' & dumped 4 bbls of cement on top of sand. 2nd plug pumped through 8 5/8" head with 5 bbls hulls, 25 bbls gells & released rubber plug & pumped 150 bbls of cement. The cement used was Common with 2% gell & 3% c.c. They recovered 2600' of 4 1/2" pipe. The plugging was accomplished by Sun Cementing. Amount of Surface Casing: 391' of 8 7/8" cement circulated with 300 bbls

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthin
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1982
7-20-82
CONSERVATION DIVISION
Wichita, Kansas

7-22-82
680-w