



KANSAS CORPORATION COMMISSION 1054422
OIL & GAS CONSERVATION DIVISION

Form ACO-1
June 2009

Form Must Be Typed
Form must be Signed
All blanks must be Filled

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

OPERATOR: License # 3895
Name: Bobcat Oilfield Services, Inc.
Address 1: 30805 COLD WATER RD
Address 2: _____
City: LOUISBURG State: KS Zip: 66053 + 8108
Contact Person: Bob Eberhart
Phone: (913) 285-0873
CONTRACTOR: License # 4339
Name: Jackson, Dale E & Sue Ellen dba Dale E. Jackson Production Co.
Wellsite Geologist: N/A
Purchaser: High Sierra Crude Oil

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil WSW SWD SIOW
 Gas D&A ENHR SIGW
 OG GSW Temp. Abd.
 CM (Coal Bed Methane)
 Cathodic Other (Core, Expl., etc.): _____

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to ENHR Conv. to SWD
 Conv. to GSW
 Plug Back: _____ Plug Back Total Depth
 Commingled Permit #: _____
 Dual Completion Permit #: _____
 SWD Permit #: _____
 ENHR Permit #: _____
 GSW Permit #: _____
3/9/2011 3/10/2011 8/16/2011
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 15-107-24391-00-00
Spot Description:
SE SW NW SE Sec. 5 Twp. 20 S. R. 23 East West
1518 Feet from North / South Line of Section
2148 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Linn
Lease Name: NE Baker Well #: H-10
Field Name: LaCygne-Cadmus
Producing Formation: Peru
Elevation: Ground: 941 Kelly Bushing: 0
Total Depth: 345 Plug Back Total Depth: _____
Amount of Surface Pipe Set and Cemented at: 20 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set: _____ Feet
If Alternate II completion, cement circulated from: 337
feet depth to: 0 w/ 50 sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content: _____ ppm Fluid volume: _____ bbls
Dewatering method used: _____
Location of fluid disposal if hauled offsite:
Operator Name: _____
Lease Name: _____ License #: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Permit #: _____

AFFIDAVIT

I am the affiant and I hereby certify that all requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Submitted Electronically

KCC Office Use ONLY

Letter of Confidentiality Received
Date: _____
 Confidential Release Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution
ALT I II III Approved by: _____ Date: 08/24/2011



1054422

Operator Name: Bobcat Oilfield Services, Inc. Lease Name: NE Baker Well #: H-10
 Sec. 5 Twp. 20 S. R. 23 East West County: Linn

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach complete copy of all Electric Wire-line Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken (Attach Additional Sheets)	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample
Samples Sent to Geological Survey	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Name	Top	Datum
Cores Taken	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Peru	275	GL
Electric Log Run	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			
Electric Log Submitted Electronically (If no, Submit Copy)	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			
List All E. Logs Run:				
Gamma Ray/Neutron/CCL				

CASING RECORD <input type="checkbox"/> New <input checked="" type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface casing	8.75	6.25	8	20	Portland	5	
Production casing	5.625	2.875	6	337	Portland/Fly Ash	50	60/40 Poz Mix

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	# Sacks Used	Type and Percent Additives
___ Perforate				
___ Protect Casing	-			
___ Plug Back TD				
___ Plug Off Zone	-			

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
3	283-308	Acid 500 gal 7.5% HCL	

TUBING RECORD:	Size:	Set At:	Packer At:	Liner Run: <input type="checkbox"/> Yes <input type="checkbox"/> No
Date of First, Resumed Production, SWD or ENHR.	Producing Method: <input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain) _____			
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio Gravity

DISPOSITION OF GAS: <input type="checkbox"/> Vented <input type="checkbox"/> Sold <input type="checkbox"/> Used on Lease (If vented, Submit ACO-18.)	METHOD OF COMPLETION: <input type="checkbox"/> Open Hole <input checked="" type="checkbox"/> Perf. <input type="checkbox"/> Dually Comp. (Submit ACO-5) <input type="checkbox"/> Commingled (Submit ACO-4) <input type="checkbox"/> Other (Specify) _____	PRODUCTION INTERVAL: _____ _____
--	---	--

Lease :	NORTH EAST BAKER	
Owner:	BOBCAT OILFIELD SERVICES INC	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface:	Cemented:	Hole Size:
20FT, 6IN	5 SACKS	8 3/4
Longstring	Cemented:	Hole Size:
337' 2 7/8	50	5 5/8
BRD		

Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: H-10
Location: SE,SW,NW,SE,S5,T20,SR23,E
County: LINN
FSL-1,485- 1518
FEL: 2,145- 2148
API#: 15-107-24230
Started: 3-9-11
Completed: 3-10-11

SN: 274'	Packer:	TD: 345'
Plugged:	Bottom Plug:	

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	TOPSOIL			
32	33	LIME			
3	36	SHALE			
4	40	BLACKSHALE			
19	59	LIME			
4	63	BLACKSHALE			
14	77	LIME			
4.5	81.5	LIME (HEAVY FLOW) (LOTS OF GAS) (SOME OIL)			
9.5	90	SANDY SHALE			
30	120	SHALE			
18	138	SANDY SHALE (DRY SAND)			
85	223	SHALE			
1	224	COAL			
10	234	SHALE			
7	241	LIME			
23	264	SHALE			
9	273	LIME			
1	274	LIGHT SANDY SHALE			
3	277	OIL SAND (SOME SHALE) (POOR BLEED) (WATER)			
5.5	282.5	OIL SAND (POOR BLEED) (WATER)			
2	284.5	OIL SAND (WATER) (SOME OIL) (GOOD BLEED)			
.5	287	OIL SAND (SHALEY) (FRACTURED) (WATER) (SOME OIL)			
5	292	OIL SAND (SOME SHALE) (GOOD BLEED)			
1.5	293.5	OIL SAND (HEAVY BLEED)			
1	294.5	OIL SAND (SHALEY) (GOOD BLEED)			
3	297.5	SANDY SHALE (SOME OIL SAND STREAKS)(POOR BLEED)			
6	303.5	OIL SAND (SHALEY) (GOOD BLEED)			
3.5	307	OIL SAND (GOOD BLEED)			
12	319	SHALE			
3	322	COAL			
6	328	SHALE			
10	338	LIME			
TD	345	SHALE			

SURFACE: 3-9-11
 SET TIME: 4:00 P.M.
 CALLED: 1:20 P.M. BECKY

LONGSTRING: 337' 2 7/8 BRD
 TD: 345'
 SET TIME: 2:30 P.M.
 CALLED: 12:45 P.M. 3-10-11 BECKY



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: H-10
Location: SE,SW,NW,SE,55,T20,SR23,E
County: LINN
FSL: 4,485 1518
FEL: 2,445 2148
API#: 15-107-24230
Started: 3-9-11
Completed: 3-10-11

Lease :	NORTH EAST BAKER
Owner:	BOBCAT OILFIELD SERVICES INC.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	280				
1	281		1	OIL SAND ("WATER")	
2	282		1.5		282.5
3	283		1.5		
4	284		1	OIL SAND ("WATER") & SOME OIL (GOOD BLEED)	284.5
5	285		1		
6	286		1	OIL SAND (OIL & WATER) (GOOD BLEED)	286.5
				OIL SAND (SHALEY) (FRACTURED) (WATER) (SOME OIL)	287
7	287		1.5		
8	288		1		
9	289		1	OIL SAND (SOME SHALE) (GOOD BLEED)	
10	290		1		
11	291		1.5		292
12	292		1.5		
				OIL SAND (HEAVY BLEED)	293.5
13	293		1		
14	294		1	OIL SAND (SHALEY) (GOOD BLEED)	294.5
15	295		1.5		
16	296		1.5	SANDY SHALE (SOME OIL SAND STREAKS) (POOR BLEED)	297.5
17	297		1.5		
				OIL SAND (SHALEY) (GOOD BLEED)	
18	298		1		
19	299		1.5		
20	300		1.5		

Avery Lumber
 P.O. BOX 66
 MOUND CITY, KS 66056
 (913) 795-2210 FAX (913) 795-2194

Merchant Copy

INVOICE

THIS COPY MUST REMAIN AT
 MERCHANT AT ALL TIMES!

Page: 1	Invoice: 10028733
Special :	Time: 12:23:04
Instructions :	Ship Date: 03/02/11
	Invoice Date: 03/04/11
Sale rep #: MAVERY MIKE	Accr rep code: Due Date: 04/05/11
Sold To: BOBCAT OILFIELD SRVC, INC C/O BOB EBERHART 30805 COLDWATER RD LOUISBURG, KS 66053	Ship To: BOBCAT OILFIELD SRVC, INC (913) 837-2823
Customer #: 3570021	Customer PC: Order By: TERRY

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
280.00	280.00	L	BAG	CPPC	PORTLAND CEMENT	7.8900 BAG	7.9900	2237.20
240.00	240.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.1000 BAG	5.1000	1224.00
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

913-837-4159
 NE Baker
 H-10
 PORTLAND GOING UP APRIL 1st
 PRICE WILL BE \$8.29 A BAG
 FLY ASH WILL STAY SAME
 M. Avery

FILLED BY	CHECKED BY	DATE SHIPPED	DRIVER	Sales total	\$3599.20
SHIP VIA LINN COUNTY				Taxable	3699.20
RECEIVED COMPLETE AND IN GOOD CONDITION				Non-taxable	0.00
X				Sales tax	233.05
				TOTAL	\$3932.25

1 - Merchant Copy

