



KANSAS CORPORATION COMMISSION 1054349
OIL & GAS CONSERVATION DIVISION

Form ACO-1
June 2009
Form Must Be Typed
Form must be Signed
All blanks must be Filled

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

OPERATOR: License # 3895
Name: Bobcat Oilfield Services, Inc.
Address 1: 30805 COLD WATER RD
Address 2: _____
City: LOUISBURG State: KS Zip: 66053 + 8108
Contact Person: Bob Eberhart
Phone: (913) 285-0873
CONTRACTOR: License # 4339
Name: Jackson, Dale E & Sue Ellen dba Dale E. Jackson Production Co.
Wellsite Geologist: N/A
Purchaser: High Sierra Crude Oil

Designate Type of Completion:

- New Well Re-Entry Workover
- Oil WSW SWD SLOW
- Gas D&A ENHR SIGW
- OG GSW Temp. Abd.
- CM (Coal Bed Methane)
- Cathodic Other (Core, Expl., etc.): _____

If Workover/Re-entry: Old Well Info as follows:

Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to ENHR Conv. to SWD
 Conv. to GSW

Plug Back: _____ Plug Back Total Depth _____
 Commingled Permit #: _____
 Dual Completion Permit #: _____
 SWD Permit #: _____
 ENHR Permit #: _____
 GSW Permit #: _____

<u>4/1/2011</u>	<u>4/5/2011</u>	<u>8/23/2011</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 15-107-24378-00-00
Spot Description: _____
NE SE NW SW Sec. 5 Twp. 20 S. R. 23 East West
1855 Feet from North / South Line of Section
1499 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Linn
Lease Name: NE Baker Well #: F-12
Field Name: LaCygne-Cadmus
Producing Formation: Peru
Elevation: Ground: 927 Kelly Bushing: 0
Total Depth: 340 Plug Back Total Depth: _____
Amount of Surface Pipe Set and Cemented at: 20 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set: _____ Feet
If Alternate II completion, cement circulated from: 331
feet depth to: 0 w/ 50 sx cmt.

Drilling Fluid Management Plan

(Data must be collected from the Reserve Pit)

Chloride content: _____ ppm Fluid volume: _____ bbls
Dewatering method used: _____
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License #: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Permit #: _____

AFFIDAVIT

I am the affiant and I hereby certify that all requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Submitted Electronically

KCC Office Use ONLY

- Letter of Confidentiality Received
Date: _____
 Confidential Release Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution
ALT I II III Approved by: Deanna Gerrico Date: 08/24/2011



1054349

Operator Name: Bobcat Oilfield Services, Inc. Lease Name: NE Baker Well #: F-12
 Sec. 5 Twp. 20 S. R. 23 East West County: Linn

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach complete copy of all Electric Wire-line Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken (Attach Additional Sheets)	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample
Samples Sent to Geological Survey	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Name	Top	Datum
Cores Taken	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Peru	269	GL
Electric Log Run	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			
Electric Log Submitted Electronically (If no, Submit Copy)	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			
List All E. Logs Run:				
Gamma Ray/Neutron/CCL				

CASING RECORD <input type="checkbox"/> New <input checked="" type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface casing	8.75	6.25	8	20	Portland	5	
Production casing	5.625	2.875	6	331	Portland/Fly Ash	50	60/40 Poz Mix

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	# Sacks Used	Type and Percent Additives
___ Perforate				
___ Protect Casing	-			
___ Plug Back TD				
___ Plug Off Zone	-			

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
3	271.5-292	Acid 500 gal 7.5% HCL	
3	298-301		

TUBING RECORD:	Size:	Set At:	Packer At:	Liner Run: <input type="checkbox"/> Yes <input type="checkbox"/> No
Date of First, Resumed Production, SWD or ENHR.	Producing Method: <input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain) _____			
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio
				Gravity

DISPOSITION OF GAS: <input type="checkbox"/> Vented <input type="checkbox"/> Sold <input type="checkbox"/> Used on Lease (If vented, Submit ACO-18.)	METHOD OF COMPLETION: <input type="checkbox"/> Open Hole <input checked="" type="checkbox"/> Perf. <input type="checkbox"/> Dually Comp. (Submit ACO-5) <input type="checkbox"/> Commingled (Submit ACO-4) <input type="checkbox"/> Other (Specify) _____	PRODUCTION INTERVAL: _____ _____
--	---	--



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: F-72
Location: N2,SE,NW,SE,SS,T20,SR23,E
County: LINN
FSL: 1,875 1855
FEL: 1,650 1499
API#: 15-107-24378-00-00
Started: 4-1-11
Completed: 4-5-11

Lease:	NORTH EAST BAKER
Owner:	BOBCAT OILFIELD SERVICES INC.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	273				
1	274		1		
2	275		1		
3	276		1	OIL SAND (SOME SHALE)	
4	277		1		
5	278		1		
6	279		1.5		280
7	280		1.5		
8	281		1.5	OIL SAND (SHALEY) (GOOD BLEED)	
9	282		2		282.5
10	283		2		
11	284		2	OIL SAND (VERY SHALEY) (FAIR BLEED)	
12	285		2		285
13	286		2	SANDY SHALE (SOME OIL SAND STREAKS) (POOR BLEED)	
14	287		2	OIL SAND (SHALEY) (GOOD BLEED)	
15	288		2	SANDY SHALE (SOME OIL SAND STREAKS) (POOR BLEED)	
16	289		2		288.5
17	290		2	OIL SAND (SHALEY) (GOOD BLEED)	
18	291		2.5		291
19	292		2		
20	293		6	SANDY SHALE	

Avery Lumber
 P.O. BOX 66
 MOUND CITY, KS 66056
 (913) 795-2210 FAX (913) 795-2194

Merchant Copy
INVOICE
 THIS COPY MUST REMAIN AT
 MERCHANT AT ALL TIMES!

Page: 1	Invoice: 10029555
Special :	Time: 15:18:58
Instructions :	Ship Date: 03/30/11
:	Invoice Date: 04/01/11
Base rep #: MAVERY MIKE	Acct rep code:
:	Due Date: 05/05/11
Sold To: BOBCAT OILFIELD SRVC, INC C/O BOB EBERHART 30805 COLDWATER RD LOUISBURG, KS 66053	Ship To: BOBCAT OILFIELD SRVC, INC (913) 837-2823 (913) 837-2823
Customer #: 3570021	Customer PO:
	Order By: TERRY

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
280.00	280.00	L	BAG	CPPC	PORTLAND CEMENT	7.9800 BAG	7.9900	2237.20
240.00	240.00	L	BAG	CPPM	POST SET FLY ASH 75#	5.1000 BAG	5.1000	1224.00
14.00	14.00	L	EA	CPQP	QUIKRETE PALLETS	17.0000 EA	17.0000	238.00

NE Baker F-12

913.837.4159

INVOICE *Ordered by Terry Direct Delivery*

FILLED BY _____ CHECKED BY _____ DATE SHIPPED _____ DRIVER _____ SHIP VIA LINN COUNTY RECEIVED COMPLETE AND IN GOOD CONDITION X	Taxable 3699.20 Non-taxable 0.00 Tax #	Sales total \$3699.20 Sales tax 233.05 TOTAL \$3932.25
---	--	---

1 - Merchant Copy

