

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-40179-00-00
Spot: NENWSESW Sec/Twnshp/Rge: 19-26S-5E
1252 feet from S Section Line, 3300 feet from E Section Line
Lease Name: HOUSTON Well #: 31
County: BUTLER Total Vertical Depth: 2655 feet

Operator License No.: 34426
Op Name: AJ'S SERVICES, A GENERAL PARTNER
Address: 924 N. TOPEKA ST.
ELDORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		75 SX
PROD	5.5	2464		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/28/2011 8:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Rcvd. from: JOHN BRICKLEY Company: AJ'S SERVICE Phone: (316) 322-7478

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 07/29/2011 11:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/83 JOINTS TBG @ 2500', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION. MIXED & PUMPED 30 SXS 60/40 POZMIX 2% GEL, 2% CC. AND DISPLACED IN CASING. CEMENT TICKET #31201. PERFORATED SQUEEZE HOLE @ 270'-271'. RIH W/TBG @ 270', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 137 SXS 60/40 MIX 2% GEL, 2% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 11:00 AM 7-29-2011.

Perfs:

Top	Bot	Thru	Comments
2464	2655	OH	

Remarks: CONSOLIDATED TICKET #31202. COMPLIANCE / 10 YR TA RULE


Plugged through: TBG

RECEIVED
AUG 17 2011

KCC WICHITA

District: 02

Signed _____



(TECHNICIAN)

Form CP-2/3
8/23/11

12K