

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20689-00-00
Spot: NENWSE Sec/Twnshp/Rge: 15-34S-21W
2230 feet from S Section Line, 1694 feet from E Section Line
Lease Name: HARPER Well #: 1-15
County: CLARK Total Vertical Depth: 5570 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4250		WITH 2 SX CMT
CIBP		5370		WITH 2 SX CMT
SURF	8.625	1208		WITH 500 SX CMT
COND	20	75		WITH 300 SX CMT
PROD	5.5	5551	2500	WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/12/2011 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: DAVID N PAULY Company: C.H. TODD Phone: (316) 250-2045

Proposed Plugging Method: CIBP @ ABOVER PERF @ 5370' & 4250' WITH 2 SX CMT. PLUG AT 1220' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/12/2011 10:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5370' WITH 2 SX CMT. SET CIBP @ 4250' WITH 2 SX CMT. 1ST PLUG AT 1220' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 90' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5424	5426		
5415	5416		
4302	4316		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

RECEIVED
AUG 18 2011
KCC WICHITA

District: 01

RECEIVED
AUG 16 2011
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

Form CP-275

8/23/11