

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-03387-00-00
Spot: S2N2NE Sec/Twnshp/Rge: 20-15S-13W
4290 feet from S Section Line, 1320 feet from E Section Line
Lease Name: HILL Well #: 8
County: RUSSELL Total Vertical Depth: 2449 feet

Operator License No.: 6883
Op Name: ROBINOWITZ OIL COMPANY, A GENE
Address: 4200 E SKELLY DR STE 620
TULSA, OK 74135

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	166	0	100 SX
PROD	5.5	2445	0	75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/17/2011 8:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Revd. from: DON DEGENHARDT Company: ROBINOWITZ OIL COMPANY Phone: (620) 587-3936

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 300# hulls - 8 sxs gel.
Perf: 875' - 450' - 160'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/17/2011 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2325' - pumped 8 sxs gel - followed with 50 sxs cement with 100# hulls.
Pulled tubing to 875' - pumped 110 sxs cement - cement circulated.
POOH. Hooked to casing and pumped 25 sxs cement - pressured up to 200# of P.S.I. Shut in.
Hooked to Braden head and pumped 25 sxs cement.
Max. P.S.I. 200#.

Perfs:

Top	Bot	Thru	Comments
2445	2450		TARKIO OPEN H/O

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #C37134.

Plugged through: TBG

District: 04

Signed Ray Dinkel
(TECHNICIAN)

CM

RECEIVED
AUG 19 2011
KCC WICHITA

Form CP-2/3

8/23/11

AUG 17 2011