

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-30185-00-00  
Spot: SWSWNE5W Sec/Twnshp/Rge: 12-10S-26W  
1413 feet from S Section Line, 3769 feet from E Section Line  
Lease Name: FLAGLER Well #: 2  
County: SHERIDAN Total Vertical Depth: 4110 feet

Operator License No.: 33268  
Op Name: RL INVESTMENT, LLC  
Address: 217 SAINT PETER ST  
MORLAND, KS 67650

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	233	0	165 SX
PROD	5.5	4100	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/04/2011 10:30 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: \_\_\_\_\_ Company: RL INVESTMENT, LLC Phone: (785) 627-5711

Proposed Plugging Method: Ordered 450 sxs 6040 pozmix - 4% gel - 600# hulls - 40 barrels of gel.  
Shoot perfs at 2242' - 1330' - 210'.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/04/2011 2:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3850' - pumped 40 BBLS gel - followed with 60 sxs cement and 250# hulls.  
Pulled tubing to 2240' - pumped 120 sxs cement with 200# hulls.  
Pulled tubing to 1120' - pumped 120 sxs cement with 150# hulls - good circulation of cement.  
Pulled tubing out - topped off with 15 sxs cement - full.  
Tied onto backside. Max. P.S.I. 400#. Full.

Perfs:

Top	Bot	Thru	Comments
3894	3899		
3852	3856		

Remarks: S.O.S. CEMENT COMPANY-TICKET #515.

Plugged through: TBG

District: 04

Signed [Signature]  
(TECHNICIAN)

CM

RECEIVED  
AUG 19 2011  
KCC WICHITA

Form CP-2/3

8/28/11

AUG 17 2011