

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-21020-00-00
Spot: SENEWSWE Sec/Twnshp/Rge: 23-13S-32W
900 feet from S Section Line, 1390 feet from E Section Line
Lease Name: CLARK TRUST Well #: 1
County: LOGAN Total Vertical Depth: 4690 feet

Operator License No.: 31900
Op Name: NOR-WEST KANSAS OIL, L.L.C.
Address: 20014 283 HWY
WAKEENEY, KS 67672

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/11/2011 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Revd. from: KIRBY Company: NOR-WEST KANSAS OIL, L.L.C. Phone: (785) 743-2769

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL Witness Type: NONE
Date/Time Plugging Completed: 08/11/2011 5:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

1st. Plug at 2510' w/25 sxs.
2nd. Plug at 1460' w/100 sxs.
3rd. Plug at 267' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

RECEIVED
AUG 19 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Ray A. Dinkel
(TECHNICIAN)

CM

Form CP-2/3
8/23/11

AUG 12 2011