

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21317-00-00
Spot: S2NWNW Sec/Twnshp/Rge: 17-14S-13W
4290 feet from S Section Line, 4620 feet from E Section Line
Lease Name: ERHLICH Well #: 1
County: RUSSELL Total Vertical Depth: 2535 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	305	0	w/130 sxs cmt
PROD	4.5	2535	0	w/100 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/12/2011 8:30 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: DAN Company: GLM COMPANY Phone: (785) 483-1307

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 300# hulls.
Perfs: 1450' - 825' - 250'.
Packer left in the well at 2230'.
This was an emergency plug.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/12/2011 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2200' - pumped 100 sxs cement.
Pulled tubing to 820' - pumped 110 sxs cement - cement circulated.
POOH. Hooked up to casing and pumped 65 sxs cement.
Cement circulated out the Braden head - casing stayed full.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #5134.

Plugged through: TBG

RECEIVED
AUG 19 2011
KCC WICHITA

District: 04

Signed RgAD-KAD
(TECHNICIAN)

CM
8/28/11
Form CP-2/3

AUG 15 2011